

CENYTRALIZATOR CANTITATI APARTAMENT PRIMAVERA STR. LIVIU REBREANU

Nr. crt.	Denumire categorie lucrari	U.M.	Hol	Hol	Baie	Camera (langa baie)	Camera	Bucatarie	Camera	Balcon	TOTAL CANTITATI
	Cod incapere		1	2	3	4	5	6	7	8	
	Suprafete (mp)		6.7	6.76	4.38	10.83	8.76	5.22	16.45	2.31	61.41
	Situatie existenta										
	Finisaj pardoseala		gresie	gresie	gresie	linoleum	linoleum	gresie	linoleum	gresie	
	Finisaj pereti		vopsea lavabila	vopsea lavabila	faianta+ vopsea lavabila	vopsea lavabila	vopsea lavabila	faianta+ vopsea lavabila	vopsea lavabila	vopsea lavabila	
	Finisaj tavane		vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	
	Situatie propusa										
1	Desfacere placaje faianta	mp	-	-	8.82	-	-	15.82	-	-	24.64
2	Desfacere linoleum	mp				10.83	8.76		16.45		36.04
3	Desfacere pardoseli din gresie	mp	6.70	6.76	4.38	-	-	5.22	-	2.31	25.37
4	Desfacere plinte din gresie	ml	6.48	10.03	-	-	-	-	-	2.10	18.61
5	Desfacere sapa de ciment	mp	6.70	6.76	4.38	10.83	8.76	5.22	16.45	2.31	61.41
6	Sapa de ciment de 3-5 cm grosime	mp	6.70	6.76	4.38	10.83	8.76	5.22	16.45	2.31	61.41
7	Amorsare suprafete pentru aplicare hidroizolatie	mp			4.38					2.31	6.69
8	Hidroizolatii la rece	mp			4.38					2.31	6.69
9	Gresie	mp	6.70	6.76	4.38	-	-	5.22	-	2.31	25.37
10	Plinta gresie	ml	6.48	10.03	-	-	-	-	-	3.70	20.21
11	Amorsare suprafete inainte de autonivelanta	mp				10.83	8.76		16.45		36.04
12	Strat suport - sapa autonivelanta	mp				10.83	8.76		16.45		36.04
13	Covor PVC , tip tarket inclusiv plinta	mp				10.83	8.76		16.45		36.04
14	Faianta	mp	-	-	15.96	-	-	16.30	-	2.88	35.14
15	Masti din rigips rez.la umiditate - mascare conducte	mp			3.00			1.50			4.50
16	Desfacere polistiren de 2 cm grosime	mp				5.90					5.90
17	Desfacere placaje rigips la pereti	mp				17.25					17.25
18	Placare parapet balcon cu placocem/rigips inclusiv vata	mp								2.88	2.88
19	Desfacere tencuieli	mp	12.93	13.20	15.96	40.81	17.97	15.82	26.64	3.85	147.18
20	Tencuieli la pereti	mp	12.93	13.20	15.96	40.81	17.97	15.82	26.64	3.85	147.18
21	Reparatii tencuieli in jurul tocurilor (ferestre)	ml			2.40	5.60	5.20	5.20	6.20	5.20	29.80
22	Glafuri ferestre din rigips verde	mp			0.36	1.12	1.12	1.12	1.12	1.12	5.96
23	Glet grosier	mp	12.93	13.20	8.16	40.81	17.97	9.33	26.64	3.85	132.89
24	Glet de finisaj	mp	25.85	26.40	8.16	40.81	35.94	9.33	53.28	7.70	207.47

CENYTRALIZATOR CANTITATI APARTAMENT PRIMAVERA STR. LIVIU REBREANU

Nr. crt.	Denumire categorie lucrari	U.M.	Hol	Hol	Baie	Camera (langa baie)	Camera	Bucatarie	Camera	Balcon	TOTAL CANTITATI
	Cod incapere		1	2	3	4	5	6	7	8	
25	Spalarea manuala a peretilor	mp	25.85	26.40	8.16	40.81	35.94	9.33	53.28	7.70	207.47
26	Amorsare suprafete de zugravit	mp	25.85	26.40	8.16	40.81	35.94	9.33	53.28	7.70	207.47
27	Protejare muchii cu profile metalice	ml			5.10			5.20		4.70	15.00
28	Zugraveli pereti si tavane	mp	25.85	26.40	8.16	40.81	35.94	9.33	53.28	7.70	207.47
29	Schela petru lucrari de finisaje	mp	6.70	6.76	4.38	10.83	8.76	5.22	16.45	2.31	61.41
30	Protejare cu folie	mp	6.70	6.76	4.38	10.83	8.76	5.22	16.45	2.31	61.41
31	Demontare usi din lemn	mp			1.68	1.68	1.68	2.16	1.89	1.68	10.77
32	Montare usi din lemn	mp			1.68	1.68	1.68	2.16	1.89		9.09
33	Montare usi din PVC	mp								1.68	1.68
34	Reparatii tencuieli in jurul tocurilor (usi)	ml			5.00	5.00	5.00	5.00	5.10	5.00	30.10
35	Montat profile trecere pardoseala	buc			1.00	1.00	1.00		1.00		4.00
36	Demontare corp iluminat	buc	1.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	9.00
37	Montare corp de iluminat plafoniera - led	buc	1.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	9.00
38	Demontare intrerupator	buc	1.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	9.00
39	Montare intrerupator	buc	1.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	9.00
40	Demontare priza	buc	1.00	1.00		2.00	2.00	1.00	2.00		9.00
41	Montare priza dubla	buc	1.00	2.00		2.00	2.00	2.00	2.00		11.00
42	Sant in tencuieli -traseu nou prize si iluminat	ml	6.00	12.00	6.00	6.00	6.00	12.00	6.00		54.00
43	Montat tub protectie dn 16 mm	ml	6.00	12.00	6.00	6.00	6.00	12.00	6.00		54.00
44	Montare conductor Fy 2,5 mm	ml		18.00				18.00			36.00
45	Montare conductor Fy 1,5 mm	ml	18.00	18.00	18.00	18.00	18.00	18.00	18.00		126.00
46	Astupare sant in tencuieli -trasee noi	ml	6.00	12.00	6.00	6.00	6.00	12.00	6.00		54.00
47	Canal cablu mascare cu sectiunea 20*40 mm	ml	10.00	10.00							20.00
48	Demontare oglinda	buc			1.00						1.00
49	Demontare vas WC	buc			1.00						1.00
50	Demontare cada	buc			1.00						1.00
51	Demontare lavoar	buc			1.00						1.00
52	Demontare baterie lavoar	buc			1.00						1.00
53	Demontare baterie cada cu dus	buc			1.00						1.00
54	Demontare spalator vase	buc						1.00			1.00
55	Demontat baterie spalator	buc						1.00			1.00
56	Demontare robineti	buc			2.00			2.00			4.00

CENYTRALIZATOR CANTITATI APARTAMENT PRIMAVERA STR. LIVIU REBREANU

Nr. crt.	Denumire categorie lucrari	U.M.	Hol	Hol	Baie	Camera (langa baie)	Camera	Bucatarie	Camera	Balcon	TOTAL CANTITATI
	Cod incapere		1	2	3	4	5	6	7	8	
57	Montat oglinda	buc			1.00						1.00
58	Montat vas WC	buc			1.00						1.00
59	Montat lavoar cu mobilier	buc			1.00						1.00
60	Montat baterie lavoar	buc			1.00						1.00
61	Montare cada inclusiv masca	buc			1.00						1.00
62	Montare baterie cada cu dus	buc			1.00						1.00
63	Montat spalator vase	buc						1.00			1.00
64	Montat baterie spalator	buc						1.00			1.00
65	Montat robineti	buc		2.00	2.00			2.00			6.00
66	Montat suport hartie igienica	buc			1.00						1.00
67	Montat etajera	buc			1.00						1.00
68	Demontare radiatoare	mp			1.00	2.00	2.00	1.00	2.00		8.00
69	Demontare console	buc			2.00	2.00	2.00	2.00	2.00		10.00
70	Montare radiator portprosop	buc			1.00						1.00
71	Radiator otel 1400x600- living	buc							1.00		1.00
72	Radiator otel 1000x600 - camere	buc				1.00	1.00				2.00
73	Radiator otel 600x600 - bucatarie	buc						1.00			1.00
74	Montare robineti tur	buc			1.00	1.00	1.00	1.00	1.00		5.00
75	Montare robineti retur	buc			1.00	1.00	1.00	1.00	1.00		5.00
76	Vopsire tevi instalatii	ml			2.00			2.00			4.00
77	Incarcare manuala moloz si desuri in saci rafie	to									3.90
78	Transport prin purtare directa moloz si deseuri	to									3.90
79	Incarcare manuala moloz si deseuri in auto	to									3.90
80	Incarcare manuala materiale in auto	to									7.85
81	Transport materiale cu auto	to									7.85
82	Descarcare din auto	to									7.85
83	Transport materiale prin purtare directa	to									7.85