

CENTRALIZATOR CANTITATI - SF. MARIA

Nr. crt.	Denumire categorie lucrari	U.M.	PARTER HOL PRINCIPAL	PARTER BIROU ASISTENT SOCIAL	PARTER CABINET MEDICAL	PARTER BIROU SEF CENTRU	PARTER GRUP SANITAR	PARTER CABINET PSIHOLOGIC	PARTER SALA MESE	PARTER - HOL +DEP.RUFE CURATE	PARTER - SPALATORIE	PARTER - CALCATORIE	PARTER - DEPOZIT RUFE MURDARE	PARTER-VESTIAR PERSONAL	PARTER VESTIAR BLOC ALIMENTAR
			P1	P2	P3	P4	P5	P6	P7	P8	P9	P10	P11	P12	P13
	Suprafete (mp)		29	8	8	9	1.5	8	15	10.28	3.5	4.2	1.8	4.2	4.2
	Situatie existenta														
	Finisaj pardoseala		gresie	gresie	gresie	gresie	gresie	gresie	gresie	gresie	gresie	gresie	gresie	gresie	gresie
	Finisaj pereti		vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	faianta+vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	faianta+vopsea lavabila	faianta+vopsea lavabila	faianta+vopsea lavabila	faianta+vopsea lavabila	faianta+vopsea lavabila
	Finisaj tavane		vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila
	Situatie propusa														
1	Glet grosier	mp	25.16	11.03	6.43	12.21	1.94	10.86	19.09	21.75	6.13	7.13	3.27	4.83	4.83
2	Glet de finisaj	mp	83.88	36.76	21.44	40.71	6.46	36.20	63.64	72.51	20.43	23.78	10.89	16.10	16.10
3	Spalarea manuala a peretilor	mp	83.88	36.76	21.44	40.71	6.46	36.20	63.64	72.51	20.43	23.78	10.89	16.10	16.10
4	Amorsare suprafete de zugravit	mp	83.88	36.76	21.44	40.71	6.46	36.20	63.64	72.51	20.43	23.78	10.89	16.10	16.10
5	Zugraveli pereti si tavane	mp	83.88	36.76	21.44	40.71	6.46	36.20	63.64	72.51	20.43	23.78	10.89	16.10	16.10
6	Schela pentru lucrari de finisaje	mp	29.00	8.00	8.00	9.00	1.50	8.00	15.00	10.28	3.50	4.20	1.80	4.20	4.20
7	Protejare cu folie	mp	29.00	8.00	8.00	9.00	1.50	8.00	15.00	10.28	3.50	4.20	1.80	4.20	4.20
8	Inlocuire geam termopan	mp													
9	Demontare priza	buc													
10	Montare priza dubla	buc													
11	Canal cablu mascare cu sectiunea 20*4	ml													
12	Incarcare manuala moloz si desuri in saci	to													
13	Transport prin purtare directa moloz si des	to													
14	Transport rutier moloz cu auto	to													
15	Incarcare manuala materiale in auto	to													
16	Transport materiale cu auto	to													
17	Descarcare din auto	to													
18	Transport materiale prin purtare directa	to													

INTOCMIT,

CENTRALIZATOR CANTITATI - SF. MARIA

Nr. crt.	Denumire categorie lucrari	U.M.	PARTER BUCATARIE CALDA	PARTER SPALATOR VASE	PARTER PREPARARE PRELIMINARA	PARTER DEPOZIT ZARZAVATURI	PARTER CAMERA FRIGIDERE	PARTER CENTRALA TERMICA	ETAJ 1 CAMERA DE ZI	ETAJ 1- DORMITOR 1+GRUP SANITAR	ETAJ 1- DORMITOR 2+GRUP SANITAR	ETAJ 1- DORMITOR 3+GRUP SANITAR	ETAJ 1- DORMITOR 4+GRUP SANITAR	ETAJ 1- IZOLATOR
			P14	P15	P16	P17	P18	P19	E1	E2	E3	E4	E5	E6
	Suprafete (mp)		10.5	4.4	6.3	3.5	1.05	5.7	30	24.5	23.5	22.5	20	16
	Situatie existenta													
	Finisaj pardoseala		gresie	gresie	gresie	gresie	gresie	gresie	parchet	parchet	parchet	parchet	parchet	gresie
	Finisaj pereti		faianta+vopsea lavabila	faianta+vopsea lavabila	faianta+vopsea lavabila	faianta+vopsea lavabila	faianta+vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila+faianta (in grup sanitar)	vopsea lavabila+faianta (in grup sanitar)	vopsea lavabila+faianta (in grup sanitar)	vopsea lavabila+faianta (in grup sanitar)	vopsea lavabila+faianta (in grup sanitar)
	Finisaj tavane		vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila
	Situatie propusa													
1	Glet grosier	mp	5.24	2.84	5.51	8.02	2.31	12.00	21.60	24.87	24.72	22.40	22.19	16.71
2	Glet de finisaj	mp	17.47	9.45	18.37	26.74	7.69	40.00	72.00	82.89	82.41	74.66	73.97	55.71
3	Spalarea manuala a peretilor	mp	17.47	9.45	18.37	26.74	7.69	40.00	72.00	82.89	82.41	74.66	73.97	55.71
4	Amorsare suprafete de zugravit	mp	17.47	9.45	18.37	26.74	7.69	40.00	72.00	82.89	82.41	74.66	73.97	55.71
5	Zugraveli pereti si tavane	mp	17.47	9.45	18.37	26.74	7.69	40.00	72.00	82.89	82.41	74.66	73.97	55.71
6	Schela pentru lucrari de finisaje	mp	10.50	4.40	6.30	3.50	1.05	5.70	30.00	24.50	23.50	22.50	20.00	16.00
7	Protejare cu folie	mp	10.50	4.40	6.30	3.50	1.05	5.70	30.00	24.50	23.50	22.50	20.00	16.00
8	Inlocuire geam termopan	mp												
9	Demontare priza	buc												
10	Montare priza dubla	buc												
11	Canal cablu mascare cu sectiunea 20*4	ml												
12	Incarcare manuala moloz si desuri in saci	to												
13	Transport prin purtare directa moloz si des	to												
14	Transport rutier moloz cu auto	to												
15	Incarcare manuala materiale in auto	to												
16	Transport materiale cu auto	to												
17	Descarcare din auto	to												
18	Transport materiale prin purtare directa	to												

Nr. crt.	Denumire categorie lucrari	U.M.	ETAJ 1-GRUP SANITAR PERSONAL	TOTAL CANTITATI
			E7	
	Suprafete (mp)		2	276.63
	Situatie existenta			
	Finisaj pardoseala		gresie	
	Finisaj pereti		vopsea lavabila+faianta	
	Finisaj tavane		vopsea lavabila	
	Situatie propusa			
1	Glet grosier	mp	1.65	304.72
2	Glet de finisaj	mp	5.49	1,015.74
3	Spalarea manuala a peretilor	mp	5.49	1015.744
4	Amorsare suprafete de zugravit	mp	5.49	1015.744
5	Zugraveli pereti si tavane	mp	5.49	1015.744
6	Schela pentru lucrari de finisaje	mp	2.00	276.63
7	Protejare cu folie	mp	2.00	276.63
8	Inlocuire geam termopan	mp		0.8944
9	Demontare priza	buc		12
10	Montare priza dubla	buc		12
11	Canal cablu mascare cu sectiunea 20*4	ml		20
12	Incarcare manuala moloz si desuri in saci	to		0.44
13	Transport prin purtare directa moloz si des	to		0.44
14	Transport rutier moloz cu auto	to		0.44
15	Incarcare manuala materiale in auto	to		4.15
16	Transport materiale cu auto	to		4.15
17	Descarcare din auto	to		4.15
18	Transport materiale prin purtare directa	to		4.15