

CENTRALIZATOR CANTITATI - AP. DUMBRAVA - STR. GURA VADULUI

Nr. crt.	Denumire categorii lucrari	U.M.	Camera	Camera (cu balcon)	Camera	Camera	Bucatarie	Baie	WC Serviciu	Camara	Hol+vestibul+sas	Logie	TOTAL CANTITATI
	Cod camera		1	2	3	4	5	6	7	8	(9+10+11)	12	
	Suprafete (mp)		17.87	13.46	10.8	9.45	6.83	2.96	0.92	1.44	12.78	3.68	80.19
	Situatie existenta												
	Finisaj pardoseala		gresie	gresie	gresie	gresie	gresie	gresie	gresie	gresie	gresie	mozaic	
	Finisaj pereti		vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	faianta+ vopsea lavabila	faianta+ vopsea lavabila	faianta+ vopsea lavabila	vopsea lavabila	vopsea lavabila	faianta+ vopsea lavabila	
	Finisaj tavane		vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	
	Situatie propusa												
1	Desfacere placaje faianta	mp	-	-	-	-	19.18	13.10	6.72	-	-	5.50	44.51
2	Desfacere pardoseli din gresie	mp	-	-	-	-	6.83	2.96	1.00	1.48	12.78	-	25.04
3	Desfacere plinte din gresie	ml	-	-	-	-	-	-	-	4.60	14.27	-	18.87
4	Desfacere sapa de ciment	mp	-	-	-	-	6.83	2.96	1.00	1.48	12.78	3.68	28.72
5	Sapa de ciment de 3 cm grosime	mp	-	-	-	-	6.83	2.96	1.00	1.48	12.78	3.68	28.72
6	Amorsare suprafete pentru aplicare hidroizolatie	mp	-	-	-	-	-	2.96	1.00	-	-	3.68	7.64
7	Hidroizolatii la rece	mp	-	-	-	-	-	2.96	1.00	-	-	3.68	7.64
8	Gresie	mp	-	-	-	-	6.83	2.96	1.00	1.48	12.78	3.68	28.72
9	Plinta gresie	ml	-	-	-	-	-	-	-	4.60	14.27	5.60	24.47
10	Faianta	mp	-	-	-	-	19.18	13.10	6.72	-	-	2.94	41.95
11	Masti din rigips rez.la umiditate - mascare conducte	mp	-	-	-	-	1.50	2.50	1.50	-	-	-	5.50
12	Desfacere tencuieli	mp	-	-	-	-	19.18	13.10	6.72	-	-	2.94	41.95
13	Refacere tencuieli	mp	-	-	-	-	19.18	13.10	6.72	-	-	2.94	41.95
14	Glet grosier	mp	11.37	9.01	8.00	7.27	1.75	7.22	3.55	2.67	8.89	2.43	62.15
15	Glet de finisaj	mp	56.84	45.07	39.98	36.34	4.38	7.22	3.55	6.68	22.22	6.08	228.35
16	Spalarea manuala a peretilor	mp	56.84	45.07	39.98	36.34	8.75	6.08	2.76	13.35	44.43	12.16	265.76
17	Amorsare suprafete de zugravit	mp	56.84	45.07	39.98	36.34	8.75	6.08	2.76	13.35	44.43	12.16	265.76
18	Protejare muchii cu profile metalice	ml	-	-	-	-	2.50	5.00	2.50	-	-	-	10.00
19	Zugraveli pereti si tavane	mp	56.84	45.07	39.98	36.34	8.75	6.08	2.76	13.35	44.43	12.16	265.76
20	Schela pemtru lucrari de finisaje	mp	17.87	13.46	10.80	9.45	6.83	2.96	0.92	1.44	12.78	3.68	80.19
21	Protejare cu folie	mp	17.87	13.46	10.80	9.45	6.83	2.96	0.92	1.44	12.78	3.68	80.19

CENTRALIZATOR CANTITATI - AP. DUMBRAVA - STR. GURA VADULUI

Nr. crt.	Denumire categorii lucrari	U.M.	Camera	Camera (cu balcon)	Camera	Camera	Bucatarie	Baie	WC Serviciu	Camara	Hol+vestibul+sas	Logie	TOTAL CANTITATI
	Cod camera		1	2	3	4	5	6	7	8	(9+10+11)	12	
22	Demontare usi din lemn	mp	1.89	1.89	1.89	1.89	1.68	1.68	1.47				12.39
23	Montare usi din lemn	mp	1.89	1.89	1.89	1.89	1.68	1.68	1.47				12.39
24	Montat profile trecere pardoseala	buc	1.00	1.00	1.00	1.00							4.00
25	Revizuire si reparare ferestre mase plastice	buc	1.00	1.00	1.00	1.00	1.00						5.00
26	Demontare corp iluminat	buc	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00			8.00
27	Montare corp de iluminat - led	buc	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00			8.00
28	Demontare intrerupator	buc	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00			8.00
29	Montare intrerupator	buc	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00			8.00
30	Demontare priza	buc	2.00	2.00	2.00	2.00	1.00					1.00	10.00
31	Montare priza dubla	buc	2.00	3.00	2.00	2.00	3.00				1.00	1.00	14.00
32	Sant in tencuieli -traseu nou prize	ml		6.00			12.00				6.00		24.00
33	Montat tub protectie dn 16 mm	ml		6.00			12.00				6.00		24.00
34	Montare conductor Fy 2,5 mm	ml		18.00			36.00				18.00		72.00
35	Astupare sant in tencuieli	ml		6.00			12.00				6.00		24.00
36	Canal cablu mascare cu sectiunea 20*40 mm	ml									20.00		20.00
37	Demontat ventilator	buc						1.00	1.00				2.00
38	Montat ventilator	buc						1.00	1.00				2.00
39	Demontare oglinda	buc						1.00	1.00				2.00
40	Demontare vas WC	buc						1.00	1.00				2.00
41	Demontare cada	buc						1.00					1.00
42	Demontare lavoar	buc						1.00	1.00				2.00
43	Demontare baterie lavoar	buc						1.00	1.00				2.00
44	Demontare baterie cada cu dus	buc						1.00					1.00
45	Demontare spalator vase	buc					1.00						1.00
46	Demontat baterie spalator	buc					1.00						1.00
47	Demontare robineti	buc						4.00	2.00				6.00
48	Montat oglinda	buc						1.00	1.00				2.00
49	Montat vas WC	buc						1.00	1.00				2.00

CENTRALIZATOR CANTITATI - AP. DUMBRAVA - STR. GURA VADULUI

Nr. crt.	Denumire categorii lucrari	U.M.	Camera	Camera (cu balcon)	Camera	Camera	Bucatarie	Baie	WC Serviciu	Camara	Hol+vestibul+sas	Logie	TOTAL CANTITATI
	Cod camera		1	2	3	4	5	6	7	8	(9+10+11)	12	
50	Montat lavoar cu mobilier	buc						1.00					1.00
51	Montat lavoar cu picior	buc							1.00				1.00
52	Montat baterie lavoar	buc						1.00	1.00				2.00
53	Montare cada inclusiv masca	buc						1.00					1.00
54	Montare baterie cada cu dus	buc						1.00					1.00
55	Montat spalator vase	buc					1.00						1.00
56	Montat baterie spalator	buc					1.00						1.00
57	Montat robineti	buc						4.00	2.00		2.00		8.00
58	Montat suport hartie igienica	buc						1.00	1.00				2.00
59	Montat etajera	buc						1.00	1.00				2.00
60	Demontare radiatoare	mp						1.00					1.00
61	Demontare console	buc						2.00					2.00
62	Demontare teava neagra inst de incalzire 1/2"	ml					5.00	5.00					10.00
63	Montare teava PPR gri cu fibra compozita 20 mm	ml					5.00	5.00					10.00
64	Montat fittinguri PP-R teu egal PP R gri 20 mm	buc					4.00	4.00					8.00
65	Montare radiator portprosop	buc						1.00					1.00
66	Vopsire radiator fonta	mp	6.48	2.88	2.88	2.88	2.88						18.00
67	Montare robineti tur	buc	1.00	1.00	1.00	1.00	1.00						5.00
68	Montare robineti retur	buc	1.00	1.00	1.00	1.00	1.00						5.00
69	Vopsire tevi instalatii	ml	3.00	3.00	2.00	2.00	3.00	4.00	2.00				19.00
70	Incarcare manuala moloz si desuri in saci	to											5.16
71	Transport prin purtare directa moloz si deseuri	to											5.16
72	Incarcare manuala moloz si deseuri in auto	to											5.16
73	Incarcare manuala materiale in auto	to											7.71
74	Transport materiale cu auto	to											7.71
75	Descarcare din auto	to											7.71
76	Transport materiale prin purtare directa	to											7.71