

CENTRALIZATOR CANTITATI - UNIREA - PARTER

Nr. crt.	Denumire categorie lucrari	U.M.	Hol parter	casa scarii	camera wc persoane dizabilitati	Camera	Cabinet	Birou	Grup sanitar	Bucatarie (kinetoterapie)	Grup sanitar	Grup sanitar	Grup sanitar	Centrala termica
			1	2	3	4	5	6	7	8	9	10	11	12
	Suprafete (mp)		45.25	8.58	3.6	6.6	12	12.08	2.7	17.77	2.49	2.44	7.21	5.87
	Situatie existenta													
	Finisaj pardoseala		gresie	gresie	gresie	parchet	parchet	parchet	gresie	gresie	gresie	gresie	gresie	gresie
	Finisaj pereti		vopsea lavabila	faianta+ vopsea lavabila	faianta+ vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	faianta+ vopsea lavabila	faianta+ vopsea lavabila	faianta+ vopsea lavabila	faianta+ vopsea lavabila	faianta+ vopsea lavabila	faianta+ vopsea lavabila
	Finisaj tavane		tavan casetat	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila
Situatie propusa														
1	Glet grosier	mp	46.09	10.63	2.83	4.78	6.94	13.60	3.36	17.54	2.51	2.47	6.33	3.97
2	Glet de finisaj	mp	153.63	35.44	9.44	15.94	23.12	45.34	11.20	58.47	8.36	8.22	21.11	13.24
3	Spalarea manuala a peretilor	mp	153.63	35.44	9.44	15.94	23.12	45.34	11.20	58.47	8.36	8.22	21.11	13.24
4	Amorsare suprafete de zugravit	mp	153.63	35.44	9.44	15.94	23.12	45.34	11.20	58.47	8.36	8.22	21.11	13.24
5	Zugraveli pereti +tavane	mp	153.63	35.44	9.44	15.94	23.12	45.34	11.20	58.47	8.36	8.22	21.11	13.24
6	Schela petru lucrari de finisaje	mp	45.25	8.58	3.60	6.60	12.00	12.08	2.70	17.77	2.49	2.44	7.21	5.87
7	Protejare cu folie	mp	45.25	8.58	3.60	6.60	12.00	12.08	2.70	17.77	2.49	2.44	7.21	5.87
8	Inlocuire tavane casetate	mp	22.63											
9	Demontare tamplarie	mp												1.68
10	Montare usa metalica rezistenta la foc 90 Minute	mp												1.68
11	Montare tamplarie din PVC (inlocuire fereastră)	mp												
12	Reparatii tencuieli in jurul tocurilor	ml												5.00
13	Protectie muchii	zeci ml												5.00
14	Demontare corpuri de iluminat	buc	2.00											
15	Montare corp iluminat tip panou led 600x600 ingrop	buc	2.00											
16	Vopsitori tevi instalatii	ml												
17	Vopsitorie confectionie metalica (balustrada si mana cu	mp		15.00										
18	Incarcare manuala moloz si desuri in saci rafie	to												
19	Transport prin purtare directa moloz si deseuri	to												
20	Incarcare manuala moloz si deseuri in auto	to												
21	Transport rutier moloz si deseuri	to												
22	Incarcare manuala materiale in auto	to												
23	Transport materiale cu auto	to												
24	Descarcare din auto	to												
25	Transport materiale prin purtare directa	to												

CENTRALIZATOR CANTITATI - UNIREA - PARTER

Nr. crt.	Denumire categorie lucrari	U.M.	Magazie	Magazie	Izolator	Sala de mese	Sala de mese (Sala terapie ocupationala)	hol intrare (windfang)	TOTAL CANTITATI PARTER
			13	14	15	16	17	18	
	Suprafete (mp)		5.75	3.64	13.44	17.42	39.4	13.56	219.8
	Situatie existenta								
	Finisaj pardoseala		gresie	gresie	gresie	parchet	parchet	gresie	
	Finisaj pereti		vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	
	Finisaj tavane		vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	
	Situatie propusa								
1	Glet grosier	mp	4.01	3.01	9.01	17.00	28.39	9.55	192.02
2	Glet de finisaj	mp	13.35	10.03	30.04	56.68	94.63	31.82	640.06
3	Spalarea manuala a peretilor	mp	13.35	10.03	30.04	56.68	94.63	31.82	640.06
4	Amorsare suprafete de zugravit	mp	13.35	10.03	30.04	56.68	94.63	31.82	640.06
5	Zugraveli pereti +tavane	mp	13.35	10.03	30.04	56.68	94.63	31.82	640.06
6	Schela petru lucrari de finisaje	mp	5.75	3.64	13.44	17.42	39.40	13.56	219.80
7	Protejare cu folie	mp	5.75	3.64	13.44	17.42	39.40	13.56	219.80
8	Inlocuire tavane casetate	mp							22.63
9	Demontare tamplarie	mp					2.40		4.08
10	Montare usa metalica rezistenta la foc 90 Minute	mp							1.68
11	Montare tamplarie din PVC (inlocuire fereastru)	mp					2.40		2.40
12	Reparatii tencuieli in jurul tocurilor	ml					6.20		11.20
13	Protectie muchii	zeci ml					6.20		1.12
14	Demontare corpuri de iluminat	buc							2.00
15	Montare corp iluminat tip panou led 600x600 ingrop	buc							2.00
16	Vopsitori tevi instalatii	ml							10.00
17	Vopsitorie confectionie metalica (balustrada si mana cu	mp							15.00
18	Incarcare manuala moloz si desuri in saci rafie	to							1.04
19	Transport prin purtare directa moloz si deseuri	to							1.04
20	Incarcare manuala moloz si deseuri in auto	to							1.04
21	Transport rutier moloz si deseuri	to							1.04
22	Incarcare manuala materiale in auto	to							6.49
23	Transport materiale cu auto	to							6.49
24	Descarcare din auto	to							6.49
25	Transport materiale prin purtare directa	to							6.49