

**CENTRALIZATORUL CANTITATILOR DE LUCRARI - CENTRUL SF ANA**

Nr. crt.	Denumire categorie lucrari	U.M.	Hol acces bucatarie ( hol secundar)	Oficiu	Bucatarie	Preparare preliminara	Camera centrala termica	Magazie zarzavat	Camera frigidere	Hol	Vestiar	Vestiar	Hol grup sanitar	Grup sanitar
PARTER														
			P10	P11	P12	P13	P14	P15	P16	P17	P18	P19	P20	P21
	<b>Suprafete ( mp)</b>		<b>26.52</b>	<b>6.5</b>	<b>21.05</b>	<b>13.16</b>	<b>12.12</b>	<b>8.02</b>	<b>5.51</b>	<b>6.05</b>	<b>3.9</b>	<b>4.96</b>	<b>3.78</b>	<b>2.4</b>
	<b>Situatie existenta</b>													
	Finisaj pardoseala		gresie	gresie	gresie	gresie	gresie	gresie	gresie	gresie	gresie	gresie	gresie	gresie
	Finisaj pereti		vopsea lavabila	faianta + vopsea lavabila	faianta + vopsea lavabila	faianta + vopsea lavabila	faianta + vopsea lavabila	faianta + vopsea lavabila	faianta + vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	faianta + vopsea lavabila
	Finisaj tavane		vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila
	<b>Situatie propusa</b>													
1	Desfacere placaje faianta	mp	-	18.78	38.02	34.47		21.83	17.75	19.66	13.90	18.02	12.73	10.67
2	Desfacere pardoseli din gresie	mp	26.52	6.50	21.05	13.16	12.12	8.02	5.51	6.21	3.90	4.96	3.78	2.40
3	Desfacere plinte din gresie	ml	23.89		-		15.03							-
4	Desfacere pardoseli din parchet	mp												
5	Desfacere sapa de ciment	mp	5.30	1.30	4.21	2.63	2.42	1.60	1.10	1.21	0.78	0.99	0.76	0.48
6	Sapa de ciment de 3 cm grosime	mp	5.30	1.30	4.21	2.63	2.42	1.60	1.10	1.21	0.78	0.99	0.76	0.48
7	Amorsare suprafete inainte de autonivelanta	mp												
8	Sapa autonivelanta	mp												
9	Amorsare suprafete inainte de hidroizolatie	mp	33.15	6.50	21.05	13.16	12.12	8.02	5.51	7.76	3.90	4.96	3.78	2.40
10	Hidroizolatii la rece	mp	33.15	6.50	21.05	13.16	12.12	8.02	5.51	7.76	3.90	4.96	3.78	2.40
11	Gresie	mp	26.52	6.50	21.05	13.16	12.12	8.02	5.51	6.21	3.90	4.96	3.78	2.40
12	Plinta gresie	ml	23.89		-		15.03							-
13	Montat covor PVC tarket inclusiv plinta	mp												
14	Faianta h=2,10	mp	-	18.78	38.02	34.47		21.83	17.75	19.66	13.90	18.02	12.73	10.67
15	Masti din rigips rez.la umiditate - mascare conducte	mp	2.28	1.13	3.60	4.00	6.42	2.28		6.27			2.28	2.20
16	Desfacere tencuieli	mp	-	9.39	19.01	17.23		10.91	8.87	9.83				
17	Refacere tencuieli	mp	-	9.39	19.01	17.23		10.91	8.87	9.83				
18	Desfacere pereti din rigips	mp											5.05	4.39
19	Refacere pereti din rigips	mp											5.05	4.39
20	Reparatii tencuieli in jurul tocurilor ( usi si ferest	ml											5.00	4.90
21	Glet grosier	mp	18.59	1.42	7.31	5.07	10.66	3.33	2.61	2.99	2.10	2.51	2.03	1.35
22	Glet de finisaj	mp	46.47	7.08	18.27	12.69	26.65	8.32	6.52	7.47	5.24	6.27	5.06	3.37

**CENTRALIZATORUL CANTITATILOR DE LUCRARI - CENTRUL SF ANA**

Nr. crt.	Denumire categorie lucrari	U.M.	Hol acces bucatarie ( hol secundar)	Oficiu	Bucatarie	Preparare preliminara	Camera centrala termica	Magazie zarzavat	Camera frigidere	Hol	Vestiar	Vestiar	Hol grup sanitar	Grup sanitar
<b>PARTER</b>														
			P10	P11	P12	P13	P14	P15	P16	P17	P18	P19	P20	P21
23	Spalarea manuala a peretilor	mp	92.94	14.15	36.53	25.37	53.31	16.63	13.05	14.93	10.48	12.55	10.13	6.74
24	Amorsare suprafete de zugravit	mp	92.94	14.15	36.53	25.37	53.31	16.63	13.05	14.93	10.48	12.55	10.13	6.74
25	Protejare muchii cu profile metalice	ml												
26	Zugraveli pereti +tavane	mp	92.94	14.15	36.53	25.37	53.31	16.63	13.05	14.93	10.48	12.55	10.13	6.74
27	Schela pentru lucrari de finisaje	mp	26.52	6.50	21.05	13.16	12.12	8.02	5.51	6.05	3.90	4.96	3.78	2.40
28	Protejare cu folie	mp	26.52	6.50	21.05	13.16	12.12	8.02	5.51	6.05	3.90	4.96	3.78	2.40
29	Demontare usi	mp							1.89					
30	Montare usi din lemn	mp												
31	Inchidere perete rigips zona usa blocata	mp							1.89					
32	montare usi din PVC	mp												
33	Montat profile trecere pardoseala	buc	2.00											
34	Demontare intrerupator	buc							1.00					
35	Montare intrerupator	buc							1.00					
36	Demontare priza	buc							2.00					
37	Montare priza dubla	buc			1.00				2.00					
38	Sant in tencuieli -traseu nou prize si iluminat	ml			6.00									
39	Montat tub protectie dn 16 mm	ml			6.00									
40	Montare conductor Fy 2,5 mm	ml			18.00									
41	Astupare sant in tencuieli	ml			6.00									
42	Demontat ventilator	buc								1.00	1.00			
43	Montat ventilator	buc								1.00	1.00			
44	Demontare oglinda	buc												
45	Demontare vas WC	buc												
46	Demontare cada dus	buc								1.00	1.00			
47	Demontare lavoar	buc												1.00
48	Demontare baterie lavoar	buc												1.00
49	Demontare baterie cada cu dus	buc								1.00	1.00			
50	Demontare tevi PPR	ml			2.00									
51	Montare tevi PPR	ml			6.00									
52	Demontare tevi scurgere PP	ml			2.00									

**CENTRALIZATORUL CANTITATILOR DE LUCRARI - CENTRUL SF ANA**

Nr. crt.	Denumire categorie lucrari	U.M.	Hol acces bucatarie ( hol secundar)	Oficiu	Bucatarie	Preparare preliminara	Camera centrala termica	Magazie zarzavat	Camera frigidere	Hol	Vestiar	Vestiar	Hol grup sanitar	Grup sanitar
<b>PARTER</b>														
			P10	P11	P12	P13	P14	P15	P16	P17	P18	P19	P20	P21
53	Montat scurgeri PP	ml			6.00									
54	Montat spalator profesional ( fara procurare sp	buc			2.00									
55	Montat baterie spalator profesional ( fara procurarespalator)				2.00									
56	Montat oglinda	buc												
57	Montat oglinda - fara procurare	buc												1.00
58	Montat vas WC, complet echipat	buc												
59	Montat vas WC, fara procurare													1.00
60	Montat lavoar cu mobilier	buc												
61	Montat baterie lavoar	buc												
62	montare lavoar fara procurare	buc												1.00
63	Montare cadita dus patrata 80x80 joasa	buc									1.00	1.00		
65	Cabina dus tip Komaq patrata 80x80	buc										1.00		
66	Montare baterie cada cu dus	buc									1.00	1.00		
67	Montat robineti	buc												
68	Demontare sifon pardoseala	buc		1.00	1.00	1.00						1.00		
69	Montat sifon pardoseala	buc		1.00	1.00	1.00						1.00		
70	Montat suport hartie igienica	buc												
71	Montat etajera	buc												
72	Demontare radiatoare	buc			4.00	2.00					1.00	1.00	1.00	1.00
73	Montare teava PPR gri cu fibra compozita 20 m	ml												
74	Montat fitinguri PP-R teu egal PP R gri 20 mm	buc												
75	Montare radiatoare fara procurare	buc			2.00	1.00					1.00	1.00	1.00	1.00
76	Incarcare manuala moloz si deseuri in saci rafie	to												
77	Transport prin purtare directa moloz si deseuri	to												
78	Incarcare manuala moloz si deseuri in auto	to												
79	Transport rutier moloz si deseuri	to												
80	Incarcare manuala materiale in auto	to												
81	Transport materiale cu auto	to												
82	Descarcare din auto	to												
83	Transport materiale prin purtare directa	to												

**CENTRALIZATORUL CANTITATILOR DE LUCRARI - CENTRUL SF ANA**

Grup sanitar	Casa scarii	Izolator	Cabinet medical	Sala kinetoterapie+grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar
<b>ETAJ 2</b>								
P22	E1-01+E2-02	E2-03+E2-04	E2-05	E2-06+E2-07	E2-09+E2-10	E2- 11+E2- 12	E2 - 13+E2 - 14	E2-15+E2-16
1.93	15.56	16.08	11.2	27.895	21.46	19.72	19.57	19.68
gresie	covor PVC	covor PVC	covor PVC	gresie grup sanitar + parchet in sala	gresie grup sanitar + parchet in dormitor	gresie grup sanitar + parchet in dormitor	gresie grup sanitar + parchet in dormitor	gresie grup sanitar + parchet in dormitor
faianta + vopsea lavabila	vopsea lavabila	faianta si vopsea lavabila in grup sanitar + vopsea lavabila in sala	faianta si vopsea lavabila in grup sanitar + vopsea lavabila in sala	faianta si vopsea lavabila in grup sanitar + vopsea lavabila in sala	faianta si vopsea lavabila in grup sanitar + vopsea lavabila in dormitor	faianta si vopsea lavabila in grup sanitar + vopsea lavabila in dormitor	faianta si vopsea lavabila in grup sanitar + vopsea lavabila in dormitor	faianta si vopsea lavabila in grup sanitar + vopsea lavabila in dormitor
vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila
10.25				11.97	14.784	15.162	15.33	15.33
1.93				2.55	3.97	4.07	4.19	4.23
-					-	-	-	-
				25.35	17.49	15.65	15.38	15.45
0.39				5.58	4.29	3.94	3.91	3.94
0.39				5.58	4.29	3.94	3.91	3.94
				25.35	17.49	15.65	15.38	15.45
				25.35	17.49	15.65	15.38	15.45
1.93				2.55	3.97	4.07	4.19	4.23
1.93				2.55	3.97	4.07	4.19	4.23
1.93				2.55	3.97	4.07	4.19	4.23
-					-	-	-	-
				25.35	17.49	15.65	15.38	15.45
10.25	0			11.97	14.784	15.162	15.33	15.33
2.20								
				5.70	5.70	5.70	5.70	5.70
				5.70	5.70	5.70	5.70	5.70
4.90				10.10	5.10	10.20	5.10	10.20
1.22	13.70	12.64	12.31	12.55	15.69	14.46	14.44	14.46
3.06	34.24	31.60	30.78	62.76	78.46	72.32	72.19	72.30

CENTRALIZATORUL CANTITATILOR DE LUCRARI - CENTRUL SF ANA

Grup sanitar	Casa scarii	Izolator	Cabinet medical	Sala kinetoterapie+grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar
<b>ETAJ 2</b>								
P22	E1-01+E2-02	E2-03+E2-04	E2-05	E2-06+E2-07	E2-09+E2-10	E2- 11+E2- 12	E2 - 13+E2 - 14	E2-15+E2-16
6.12	68.48	63.20	61.56	62.76	78.46	72.32	72.19	72.30
6.12	68.48	63.20	61.56	62.76	78.46	72.32	72.19	72.30
				9.25	9.25	9.25	9.25	9.25
6.12	<b>68.48</b>	<b>63.2</b>	<b>61.56</b>	<b>62.7625</b>	<b>78.45925</b>	<b>72.315</b>	<b>72.19</b>	<b>72.3</b>
1.93	15.56	16.08	11.20	27.90	21.46	19.72	19.57	19.68
1.93	15.56	16.08	11.20	27.90	21.46	19.72	19.57	19.68
				3.57	1.89	3.78	1.89	3.78
				1.89	1.89	1.89	1.89	1.89
				1.68		1.89		1.89
					1.00	1.00	1.00	1.00
					1.00	1.00	1.00	1.00
					1.00	1.00	1.00	1.00
					1.00	1.00	1.00	1.00
				1.00	1.00	1.00	1.00	1.00
				1.00	1.00	1.00	1.00	1.00
				1.00	1.00	1.00	1.00	1.00
				1.00	1.00	1.00	1.00	1.00
1.00				1.00	1.00	1.00	1.00	1.00
1.00				1.00	1.00	1.00	1.00	1.00
				1.00	1.00	1.00	1.00	1.00



**CENTRALIZATORUL CANTITATILOR DE LUCRARI - CENTRUL SF ANA**

Dormitor + grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar	TOTAL CANTITATI
E2-18+E2-19	E2-21+E2-22	E2-23+E2-24	E2-25+E2-26	E2-27+E2-28	E2-29+E2-30	
<b>19.26</b>	<b>19.46</b>	<b>19.38</b>	<b>19.64</b>	<b>19.91</b>	<b>19.74</b>	<b>384.455</b>
gresie grup sanitar + parchet in dormitor	gresie grup sanitar + parchet in dormitor	gresie grup sanitar + parchet in dormitor	gresie grup sanitar + parchet in dormitor	gresie grup sanitar + parchet in dormitor	gresie grup sanitar + parchet in dormitor	
faianta si vopsea lavabila in grup sanitar + vopsea lavabila in dormitor	faianta si vopsea lavabila in grup sanitar + vopsea lavabila in dormitor	faianta si vopsea lavabila in grup sanitar + vopsea lavabila in dormitor	faianta si vopsea lavabila in grup sanitar + vopsea lavabila in dormitor	faianta si vopsea lavabila in grup sanitar + vopsea lavabila in dormitor	faianta si vopsea lavabila in grup sanitar + vopsea lavabila in dormitor	
vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	
<b>14.07</b>	14.7	14.49	14.7	15.54	15.33	<b>377.47</b>
<b>3.95</b>	4.01	4.13	4.19	4.26	4.25	<b>159.86</b>
-	-	-	-	-	-	<b>38.92</b>
15.31	15.45	15.25	15.45	15.65	15.49	<b>181.92</b>
3.85	3.89	3.88	3.93	3.98	3.95	<b>68.32</b>
3.85	3.89	3.88	3.93	3.98	3.95	<b>68.32</b>
15.31	15.45	15.25	15.45	15.65	15.49	<b>181.92</b>
15.31	15.45	15.25	15.45	15.65	15.49	<b>181.92</b>
3.95	4.01	4.13	4.19	4.26	4.25	<b>168.04</b>
3.95	4.01	4.13	4.19	4.26	4.25	<b>168.04</b>
3.95	4.01	4.13	4.19	4.26	4.25	<b>159.86</b>
-	-	-	-	-	-	<b>38.92</b>
15.31	15.45	15.25	15.45	15.65	15.49	<b>181.92</b>
<b>14.07</b>	14.7	14.49	14.7	15.54	15.33	<b>377.47</b>
						<b>32.66</b>
						<b>75.25</b>
						<b>75.25</b>
5.70	5.70	5.70	5.70	5.70	5.70	<b>72.14</b>
5.70	5.70	5.70	5.70	5.70	5.70	<b>72.14</b>
10.20	10.20	10.20	10.20	10.20	10.20	<b>116.70</b>
14.57	14.28	14.23	14.35	14.57	14.28	<b>257.69</b>
72.84	71.41	71.13	71.75	72.83	71.42	<b>1,042.47</b>

**CENTRALIZATORUL CANTITATILOR DE LUCRARI - CENTRUL SF ANA**

Dormitor + grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar	TOTAL CANTITATI
E2-18+E2-19	E2-21+E2-22	E2-23+E2-24	E2-25+E2-26	E2-27+E2-28	E2-29+E2-30	
72.84	71.41	71.13	71.75	72.83	71.42	<b>1,295.54</b>
72.84	71.41	71.13	71.75	72.83	71.42	<b>1,295.54</b>
9.25	9.25	9.25	9.25	9.25	9.25	<b>101.75</b>
<b>72.84</b>	<b>71.41</b>	<b>71.13</b>	<b>71.75</b>	<b>72.8275</b>	<b>71.42</b>	<b>1,295.54</b>
19.26	19.46	19.38	19.64	19.91	19.74	<b>384.46</b>
19.26	19.46	19.38	19.64	19.91	19.74	<b>384.46</b>
3.78	3.78	3.78	3.78	1.89	1.89	<b>35.70</b>
1.89	1.89	1.89	1.89	1.89	1.89	<b>20.79</b>
						<b>1.89</b>
1.89	1.89	1.89	1.89			<b>13.02</b>
						<b>2.00</b>
1.00	1.00	1.00	1.00	1.00	1.00	<b>11.00</b>
1.00	1.00	1.00	1.00	1.00	1.00	<b>11.00</b>
1.00	1.00	1.00	1.00	1.00	1.00	<b>12.00</b>
1.00	1.00	1.00	1.00	1.00	1.00	<b>13.00</b>
						<b>6.00</b>
						<b>6.00</b>
						<b>18.00</b>
						<b>6.00</b>
1.00	1.00	1.00	1.00	1.00	1.00	<b>13.00</b>
1.00	1.00	1.00	1.00	1.00	1.00	<b>13.00</b>
1.00	1.00	1.00	1.00	1.00	1.00	<b>11.00</b>
1.00	1.00	1.00	1.00	1.00	1.00	<b>11.00</b>
1.00	1.00	1.00	1.00	1.00	1.00	<b>13.00</b>
1.00	1.00	1.00	1.00	1.00	1.00	<b>13.00</b>
1.00	1.00	1.00	1.00	1.00	1.00	<b>13.00</b>
1.00	1.00	1.00	1.00	1.00	1.00	<b>13.00</b>
						<b>2.00</b>
						<b>6.00</b>
						<b>2.00</b>



**CENTRALIZATORUL CANTITATILOR DE LUCRARI - CENTRUL SF ANA**

Dormitor + grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar	Dormitor + grup sanitar	TOTAL CANTITATI
E2-18+E2-19	E2-21+E2-22	E2-23+E2-24	E2-25+E2-26	E2-27+E2-28	E2-29+E2-30	
						6.00
						2.00
						2.00
1.00	1.00	1.00	1.00	1.00	1.00	11.00
						2.00
1.00	1.00	1.00	1.00	1.00	1.00	11.00
						2.00
1.00	1.00	1.00	1.00	1.00	1.00	11.00
1.00	1.00	1.00	1.00	1.00	1.00	11.00
						2.00
1.00	1.00	1.00	1.00	1.00	1.00	13.00
1.00	1.00	1.00	1.00	1.00	1.00	12.00
1.00	1.00	1.00	1.00	1.00	1.00	13.00
2.00	2.00	2.00	2.00	2.00	2.00	22.00
1.00	1.00	1.00	1.00	1.00	1.00	15.00
1.00	1.00	1.00	1.00	1.00	1.00	15.00
1.00	1.00	1.00	1.00	1.00	1.00	11.00
1.00	1.00	1.00	1.00	1.00	1.00	11.00
1.00	1.00	1.00	1.00	1.00	1.00	22.00
6.00	6.00	6.00	6.00	6.00	6.00	66.00
2.00	2.00	2.00	2.00	2.00	2.00	22.00
1.00	1.00	1.00	1.00	1.00	1.00	19.00
						25.644
						25.644
						25.644
						25.644
						29.500
						29.500
						29.500
						29.500