

CENTRALIZATOR CANTITATI AP. VULTURUL - STR. FIZICIENILOR

Nr. c	Denumire categorii lucrari	U.M.	Camera	Camera	Camera	Bucatarie	Camara	Baie	Debara	WC Serviciu	Hol+vestibul+sas	Logie	TOTAL CANTITATI
	Cod incapere		1	2	3	4	5	6	7	8	(9+10+11)	12	
	Suprafete (mp)		17.52	11	10.54	7.15	0.95	4.2	0.85	1.77	10.09	2.84	66.91
	Situatie existenta												
	Finisaj pardoseala		parchet	parchet	parchet	gresie	gresie	gresie	gresie	gresie	gresie	gresie	
	Finisaj pereti		vopsea lavabila	vopsea lavabila	vopsea lavabila	faianta+ vopsea lavabila	vopsea lavabila	faianta+ vopsea lavabila	vopsea lavabila	faianta+ vopsea lavabila	vopsea lavabila	vopsea lavabila	
	Finisaj tavane		vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	
	Situatie propusa												
1	Desfacere placaje faianta	mp	-	-	-	15.22		15.04		8.32	-		38.58
2	Desfacere pardoseli din gresie	mp	-	-	-	7.15	0.95	4.20	0.85	1.77	10.09	2.84	27.85
3	Desfacere plinte din gresie	ml	-	-	-	-	2.90	-	2.75		15.65	6.40	27.70
4	Desfacere pardoseli din parhet	mp	17.52	11.00	10.54								39.06
5	Desfacere sapa de ciment	mp	17.52	11.00	10.54	7.15	0.95	4.20	0.85	1.77	10.09	2.84	66.91
6	Sapa de ciment de 3 cm grosime	mp	17.52	11.00	10.54	7.15	0.95	4.20	0.85	1.77	10.09	2.84	66.91
7	Amorsare suprafete inainte de autonivelanta	mp	17.52	11.00	10.54								39.06
8	Sapa autonivelanta	mp	17.52	11.00	10.54								39.06
9	Amorsa hidroizolatii	mp						4.20		1.77		2.84	8.81
10	Hidroizolatii la rece	mp						4.20		1.77		2.84	8.81
11	Gresie	mp	-	-	-	7.15	0.95	4.20	0.85	1.77	10.09	2.84	27.85
12	Plinta gresie	ml	-	-	-	-	2.90	-	2.75		15.65	6.40	27.70
13	Montat covor PVC tarket inclusiv plinta	mp	17.52	11.00	10.54								39.06
14	Faianta (bucat h=1 m front de lucru + 1 m +1 m+ baie h=2,10)	mp	-	-	-	4.86		19.74		10.92	-		35.52
15	Masti din rigips rez.la umiditate - mascare conducte	mp				1.28		3.50	2.00	3.00			9.78
16	Desfacere tencuieli	mp	22.69	9.52	9.62	5.99	4.16	3.95	3.93	2.24	13.47	7.26	82.81
17	Refacere tencuieli	mp	22.69	9.52	9.62	5.99	4.16	3.95	3.93	2.24	13.47	7.26	82.81
18	Reparatii tencuieli in jurul tocurelor (ferestre)	ml	6.60	6.00	6.00	5.00						7	30.60
19	Reparatii tencuieli in jurul tocurelor (usi)	ml	5.10	5.00	5.00	5.00	5.00	5.00		5.00			35.10
20	Glet grosier	mp	22.69	9.52	9.62	5.99	4.16	3.95	3.93	2.24	13.47	7.26	82.81
21	Glet de finisaj	mp	45.38	19.04	19.24	11.97	8.33	7.89	7.86	4.47	26.95	14.51	165.63
22	Spalarea manuala a peretilor	mp	45.38	19.04	19.24	11.97	8.33	7.89	7.86	4.47	26.95	14.51	165.63

CENTRALIZATOR CANTITATI AP. VULTURUL - STR. FIZICIENILOR

Nr. c	Denumire categorii lucrari	U.M.	Camera	Camera	Camera	Bucatarie	Camara	Baie	Debara	WC Serviciu	Hol+vestibul+sas	Logie	TOTAL CANTITATI
	Cod incapere		1	2	3	4	5	6	7	8	(9+10+11)	12	
23	Amorsare suprafete de zugravit	mp	45.38	19.04	19.24	11.97	8.33	7.89	7.86	4.47	26.95	14.51	165.63
24	Zugraveli pereti si tavane	mp	45.38	19.04	19.24	11.97	8.33	7.89	7.86	4.47	26.95	14.51	165.63
25	Schela pemtru lucrari de finisaje	mp	17.52	11.00	10.54	7.15	0.95	4.20	0.85	1.77	10.09	2.84	66.91
26	Protejare cu folie	mp	17.52	11.00	10.54	7.15	0.95	4.20	0.85	1.77	10.09	2.84	66.91
27	Demontare usi din lemn	mp	1.89	1.68	1.68	1.68	1.68	1.68	2.50	1.68			14.47
28	Montare usi din lemn	mp	1.89	1.68	1.68	1.68	1.68	1.68		1.68			11.97
29	Montat profile trecere pardoseala	buc	1.00	1.00	1.00								3.00
30	Revizuire si reparare ferestre mase plastice	mp	1.50	1.50	1.50	1.50							6.00
31	Demontare corp iluminat	buc	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	3.00		11.00
32	Montare corp de iluminat - led	buc	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	3.00		11.00
33	Demontare intrerupator	buc	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	2.00		10.00
34	Montare intrerupator	buc	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	2.00		10.00
35	Demontare priza	buc	2.00	2.00	2.00	2.00						1.00	9.00
36	Montare priza dubla	buc	3.00	2.00	2.00	2.00			1.00			1.00	11.00
37	Sant in tencuieli -traseu nou prize si iluminat	ml	6.00			6.00			6.00		6.00		24.00
38	Montat tub protectie dn 16 mm	ml	6.00			6.00			6.00		6.00		24.00
39	Montare conductor Fy 2,5 mm	ml	18.00			18.00			18.00				54.00
40	Montare conductor Fy 1,5 mm	ml									18.00		18.00
41	Astupare sant in tencuieli	ml	6.00			6.00			6.00		6.00		24.00
42	Canal cablu mascare cu sectiunea 20*40 mm	ml									20.00		20.00
43	Demontat ventilator	buc						1.00		1.00			2.00
44	Montat ventilator	buc						1.00		1.00			2.00
45	Demontare oglinda	buc						1.00		1.00			2.00
46	Demontare vas WC	buc						1.00		1.00			2.00
47	Demontare cada	buc						1.00					1.00
48	Demontare lavoar	buc						1.00		1.00			2.00
49	Demontare baterie lavoar	buc						1.00		1.00			2.00
50	Demontare baterie cada cu dus	buc						1.00					1.00
51	Demontare spalator vase	buc				1.00							1.00
52	Demontat baterie spalator	buc				1.00							1.00

CENTRALIZATOR CANTITATI AP. VULTURUL - STR. FIZICIENILOR

Nr. c	Denumire categorii lucrari	U.M.	Camera	Camera	Camera	Bucatarie	Camara	Baie	Debara	WC Serviciu	Hol+vestibul+sas	Logie	TOTAL CANTITATI
	Cod incapere		1	2	3	4	5	6	7	8	(9+10+11)	12	
53	Demontare robineti	buc				2.00		4.00		2.00			8.00
54	Montat oglinda	buc						1.00		1.00			2.00
55	Montat vas WC	buc						1.00		1.00			2.00
56	Montat lavoar cu picior	buc								1.00			1.00
57	Montat lavoar cu mobilier	buc						1.00					1.00
58	Montat baterie lavoar	buc						1.00		1.00			2.00
59	Montare cada inclusiv masca	buc						1.00					1.00
60	Montare baterie cada cu dus	buc						1.00					1.00
61	Montare spalator vase	buc				1.00							1.00
62	Mmontat baterie spalator	buc				1.00							1.00
63	Montat robineti	buc				2.00		4.00					6.00
64	Montat suport hartie igienica	buc						1.00		1.00			2.00
65	Montat etajera	buc						1.00		1.00			2.00
66	Demontare radiatoare	mp	2.00	2.00	2.00	1.00		1.00					8.00
67	Demontare console	buc	2.00	2.00	2.00	2.00		2.00					10.00
68	Demontare teava pexal 1/2"	ml	10.00	10.00	10.00	10.00							40.00
69	Demontare teava neagra inst de incalzire 1/2"	ml						10.00					10.00
70	Montare teava PPR gri cu fibra compozita 20 mm	ml	10.00	10.00	10.00	10.00		10.00					50.00
71	Montat fittinguri PP-R teu egal PP R gri 20 mm	buc	2.00	2.00	2.00	2.00		4.00					12.00
72	Montare radiator portprosop	buc						1.00					1.00
73	Radiator otel 1400x600- living	buc	1.00										1.00
74	Radiator otel 1000x600 - camere	buc		1.00	1.00								2.00
75	Radiator otel 600x600 - bucatarie	buc				1.00							1.00
76	Montare robineti tur retur	buc	1.00	1.00	1.00	1.00		1.00					5.00
77	Montare robineti tur retur	buc	1.00	1.00	1.00	1.00		1.00					5.00
78	Incarcare manuala moloz si desuri in saci rafie	to											4.43
79	Transport prin purtare directa moloz si deseuri	to											4.43

CENTRALIZATOR CANTITATI AP. VULTURUL - STR. FIZICIENILOR

Nr. c	Denumire categorii lucrari	U.M.	Camera	Camera	Camera	Bucatarie	Camara	Baie	Debara	WC Serviciu	Hol+vestibul+sas	Logie	TOTAL CANTITATI
	Cod incapere		1	2	3	4	5	6	7	8	(9+10+11)	12	
80	Incarcare manuala moloz si deseuri in auto	to											4.43
81	Incarcare manuala materiale in auto	to											7.48
82	Transport materiale cu auto	to											7.48
83	Descarcare din auto	to											7.48
84	Transport materiale prin purtare directa	to											7.48

Intocmit,