

CENTRALIZATOR CANTITATI - SIRUDAS AP. 534

Nr. crt.	Denumire categorii lucrari	U.M.	Sufragerie	Bucatarie	Baie	Vestibul	Debara	Logie	TOTAL CANTITATI
			1	2	3	4	5	6	
	Suprafete (mp)		19.46	4.04	3.04	1.52	1.71	3.62	33.39
	Situatie existenta								
	Finisaj pardoseala		parchet	gresie	gresie	gresie	gresie	mozaic	
	Finisaj pereti		vopsea lavabila	vopsea lavabila	faianta+ vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila+faianta	
	Finisaj tavane		vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	
	Situatie propusa								
1	Glet grosier	mp	18.37	6.99	0.91	2.82	4.14	4.46	37.69
2	Glet de finisaj	mp	61.23	23.28	3.04	9.42	13.81	14.86	125.64
3	Spalarea manuala a peretilor	mp	61.23	23.28	3.04	9.42	13.81	14.86	125.64
4	Amorsare suprafete de zugravit	mp	61.23	23.28	3.04	9.42	13.81	14.86	125.64
5	Zugraveli pereti si tavane	mp	61.23	23.28	3.04	9.42	13.81	14.86	125.64
6	Schela petru lucrari de finisaje	mp	19.46	4.04	3.04	1.52	1.71	3.62	33.39
7	Protejare cu folie	mp	19.46	4.04	3.04	1.52	1.71	3.62	33.39
9	Vopsire radiator fonta	mp	2.88	1.92					4.80
9	Vopsitori tevi instalatii	ml							16.50
10	Incarcare manuala moloz si desuri in saci rafie	to							0.25
11	Transport prin purtare directa moloz si deseuri	to							0.25
12	Incarcare manuala moloz si deseuri in auto	to							0.25
13	Transport rutier moloz si deseuri	to							0.25
14	Incarcare manuala materiale in auto	to							0.50
15	Transport materiale cu auto	to							0.50
16	Descarcare din auto	to							0.50
17	Transport materiale prin purtare directa	to							0.50

INTOCMIT,