

CENTRALIZATOR CANTITATI - APARTAMENT ARENA - STR. TINA PETRE

Nr. crt.	Denumire categorie lucrari	U.M.	Bucatarie	Camera ( dormitor langa bucatarie)	Camera (living)	Camera ( dormitor langa baie)	Baie	Sas	Debara	Vestibul	WC Serviciu	Logie	TOTAL CANTITATI
			1	2	3	4	6	5	7	8	9	10	
	<b>Suprafete ( mp)</b>		<b>8.64</b>	<b>9.00</b>	<b>20.48</b>	<b>12.05</b>	<b>4.20</b>	<b>1.30</b>	<b>0.57</b>	<b>8.47</b>	<b>2.05</b>	<b>5.87</b>	<b>72.63</b>
	<b>Situatie existenta</b>												
	Finisaj pardoseala		gresie	parchet	parchet	parchet	gresie	gresie	gresie	gresie	gresie	gresie	
	Finisaj pereti		faianta h=1,55 m+ vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	faiantah =1,82+ vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	faianta h=1,52+ vopsea lavabila	vopsea lavabila	
	Finisaj tavane		vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	
<b>Situatie propusa</b>													
1	Desfacere placaje faianta	mp	17.21	-	-	-	13.47				8.06		<b>38.73</b>
2	Desfacere pardoseli din gresie	mp	8.64	-	-	-	4.20	1.30	0.57	8.47	2.05	5.87	<b>31.10</b>
3	Desfacere plinte din gresie	ml	-	-	-	-	-	1.26	2.23	9.70		15.50	<b>28.69</b>
4	Desfacere pardoseli din parhet	mp		9.00	20.48	12.05							<b>41.53</b>
5	Desfacere sapa de ciment	mp	8.64	9.00	20.48	12.05	4.20	1.30	0.57	8.47	2.05	5.87	<b>72.63</b>
6	Sapa de ciment de 3 cm grosime	mp	8.64	9.00	20.48	12.05	4.20	1.30	0.57	8.47	2.05	5.87	<b>72.63</b>
7	Amorsare suprafete inainte de autonivelanta	mp		9.00	20.48	12.05							<b>41.53</b>
8	Sapa autonivelanta	mp		9.00	20.48	12.05							<b>41.53</b>
9	Amorsare suprafete hidroizolatii la rece	mp					4.20				2.05	5.87	<b>12.12</b>
10	Hidroizolatii la rece - bai / balcoane /logii	mp					4.20				2.05	5.87	<b>12.12</b>
11	Gresie	mp	8.64	-	-	-	4.20	1.30	0.57	8.47	2.05	5.87	<b>31.10</b>
12	Plinta gresie	ml	-	-	-	-	-	1.26	2.23	9.70		15.50	<b>28.69</b>
13	Montat covor PVC tarket inclusiv plinta	mp		9.00	20.48	12.05							<b>41.53</b>
14	Faianta (bucat h=1 m front de lucru + 0,6 m +1 m+ baie h=2,10)	mp	5.25	-	-	-	15.76				14.91		<b>35.92</b>
15	Masti din rigips rez.la umiditate - mascare conducte	mp	2.04				4.00				2.55		<b>8.59</b>
16	Desfacere tencuieli	mp	15.22	7.36	12.19	8.72	19.74	0.95	1.25	5.55	10.92	14.51	<b>96.41</b>
17	Refacere tencuieli	mp	15.22	7.36	12.19	8.72	19.74	0.95	1.25	5.55	10.92	14.51	<b>96.41</b>
18	Reparatii tencuieli in jurul tocurilor ( ferestre )	ml	5.00	5.10	5.42	5.84						5.42	<b>26.78</b>
19	Glet grosier	mp	16.04	18.41	30.49	21.81	7.89	0.95	1.25	5.55	4.47	14.51	<b>121.36</b>

CENTRALIZATOR CANTITATI - APARTAMENT ARENA - STR. TINA PETRE

Nr. crt.	Denumire categorii lucrari	U.M.	Bucatarie	Camera ( dormitor langa bucatarie)	Camera (living)	Camera ( dormitor langa baie)	Baie	Sas	Debara	Vestibul	WC Serviciu	Logie	TOTAL CANTITATI
20	Glet de finisaj	mp	32.08	36.82	60.97	43.62	7.89	4.74	6.26	27.73	4.47	22.52	247.10
21	Spalarea manuala a peretilor	mp	32.08	36.82	60.97	43.62	7.89	4.74	6.26	27.73	4.47	22.52	247.10
22	Amorsare suprafete de zugravit	mp	32.08	36.82	60.97	43.62	7.89	4.74	6.26	27.73	4.47	22.52	247.10
23	Zugraveli pereti si tavane	mp	32.08	36.82	60.97	43.62	7.89	4.74	6.26	27.73	4.47	22.52	247.10
24	Schela pemtru lucrari de finisaje	mp	8.64	9.00	20.48	12.05	4.20	1.30	0.57	8.47	2.05	5.87	72.63
25	Protejare cu folie	mp	8.64	9.00	20.48	12.05	4.20	1.30	0.57	8.47	2.05	5.87	72.63
26	Carotare pereti AC/hote	buc	1.00	1.00									2.00
27	Montat profile trecere pardoseala	buc		1.00	1.00	1.00							3.00
28	Demontare corp iluminat	buc	1.00	1.00	1.00	1.00	1.00	1.00		2.00	1.00		9.00
29	Montare corp de iluminat - led	buc	1.00	1.00	1.00	1.00	1.00	1.00		2.00	1.00		9.00
30	Demontare intrerupator	buc	1.00	1.00	1.00	1.00	1.00	1.00		2.00	1.00		9.00
31	Montare intrerupator	buc	1.00	1.00	1.00	1.00	1.00	1.00		2.00	1.00		9.00
32	Demontare priza	buc	2.00	2.00	2.00	2.00							8.00
33	Montare priza dubla	buc	3.00	3.00	4.00	4.00							14.00
34	Demontare tablou electric	buc											1.00
35	Montare tablou electric	buc											1.00
36	Sant in tencuieli -traseu nou prize si iluminat	ml	15.00	20.00	15.00	20.00	10.00	10.00		20.00	10.00		120.00
37	Demontare tuburi electrice	ml	15.00	20.00	15.00	20.00	10.00	10.00		20.00	10.00		120.00
38	Demontare conductori electrice	ml	45.00	60.00	45.00	60.00	30.00	30.00		60.00	30.00		360.00
39	Montat tub protectie dn 16 mm	ml	15.00	20.00	15.00	20.00	10.00	10.00		20.00	10.00		120.00
40	Montare conductor Fy 2,5 mm	ml	22.50	30.00	22.50	30.00	15.00	15.00		30.00	15.00		180.00
41	Montare conductor Fy 1,5 mm	ml	22.50	30.00	22.50	30.00	15.00	15.00		30.00	15.00		180.00
42	Astupare sant in tencuieli	ml	15.00	20.00	15.00	20.00	10.00	10.00		20.00	10.00		120.00
43	Canal cablu mascare cu sectiunea 20*40 mm	ml								22.00			22.00
44	Demontat ventilator	buc					1.00				1.00		2.00
45	Montat ventilator	buc					1.00				1.00		2.00
46	Demontare oglinda	buc					1.00				1.00		2.00
47	Demontare vas WC	buc					1.00				1.00		2.00
48	Demontare cada	buc					1.00						1.00

## CENTRALIZATOR CANTITATI - APARTAMENT ARENA - STR. TINA PETRE

Nr. crt.	Denumire categorii lucrari	U.M.	Bucatarie	Camera ( dormitor langa bucatarie)	Camera (living)	Camera ( dormitor langa baie)	Baie	Sas	Debara	Vestibul	WC Serviciu	Logie	TOTAL CANTITATI
			1	2	3	4	6	5	7	8	9	10	
49	Demontare lavoar	buc					1.00				1.00		2.00
50	Demontare baterie lavoar	buc					1.00				1.00		2.00
51	Demontare baterie cada cu dus	buc					1.00						1.00
52	Demontare spalator vase	buc	1.00										1.00
53	Demontat baterie spalator	buc	1.00										1.00
54	Demontare robineti	buc	2.00				2.00				2.00		6.00
55	Montat oglinda	buc					1.00				1.00		2.00
56	Montat WC complet echipat	buc					1.00				1.00		2.00
57	Montat lavoar cu picior	buc									1.00		1.00
58	Montat lavoar cu mobilier inclus	buc					1.00						1.00
59	Montat baterie lavoar	buc					1.00				1.00		2.00
60	Montare cada inclusiv masca	buc					1.00						1.00
61	Montare baterie cada cu dus	buc					1.00						1.00
62	Montare spalator vase	buc	1.00										1.00
63	Mmontat baterie spalator	buc	1.00										1.00
64	Montat robineti	buc	2.00				4.00						6.00
65	Montat suport hartie igienica	buc					1.00				1.00		2.00
66	Montat etajera	buc					1.00				1.00		2.00
67	Demontare radiatoare	buc	1.00	2.00	2.00	2.00	1.00						8.00
68	Demontare console	buc	2.00	2.00	2.00	2.00	2.00						10.00
69	Montat tub de scurgere Dn 50mm	ml					2.00				2.00		4.00
70	Demontare teava neagra inst de incalzire 1/2"	ml	14.00	15.00	14.00	12.00	8.00						63.00
71	Montare teava PPR gri cu fibra compozita 20 m	ml	14.00	15.00	14.00	12.00	8.00						63.00
72	Montat fittinguri PP-R teu egal PP R gri 20 mm	buc	4.00	4.00	2.00	4.00	10.00						24.00
73	Montare radiator portprosop	buc					1.00						1.00
74	Radiator otel 1400x600- living	buc			1.00								1.00
75	Radiator otel 1000x600 - camere	buc		1.00		1.00							2.00
76	Rdaiator otel 600x600	buc	1.00										1.00
77	Montare robineti tur retur	buc	1.00	1.00	1.00	1.00	1.00						5.00

## CENTRALIZATOR CANTITATI - APARTAMENT ARENA - STR. TINA PETRE

Nr. crt.	Denumire categorie lucrari	U.M.	Bucatarie	Camera ( dormitor langa bucatarie)	Camera (living)	Camera ( dormitor langa baie)	Baie	Sas	Debara	Vestibul	WC Serviciu	Logie	TOTAL CANTITATI
			1	2	3	4	6	5	7	8	9	10	
78	Montare robineti tur retur	buc	1.00	1.00	1.00	1.00	1.00						5.00
79	Incarcare manuala moloz si desuri in saci rafie	to											5.30
80	Transport prin purtare directa moloz si deseuri	to											5.30
81	Incarcare manuala moloz si deseuri in auto	to											5.30
82	Incarcare manuala materiale in auto	to											8.14
83	Transport materiale cu auto	to											8.14
84	Descarcare din auto	to											8.14
85	Transport materiale prin purtare directa	to											8.14