

CENTRALIZATOR CANTITATI AP. COLIBRI - STR. JEAN STERIADI

Nr. crt.	Denumire categorii lucrari	U.M.	Camera de zi	Camera	Bucatarie	Baie	Vestibul	Camara	Hol	Debara	Balcon	TOTAL
			1	2	3	4	5	6	7	8	9	9
	Suprafete (mp)		18.69	11.6245	7.5895	4.07	2.57	0.82	4.35	1.36	3.1415	54.2155
	Situatie existenta											
	Finisaj pardoseala		parchet	parchet	gresie	gresie	gresie	gresie	gresie	gresie	gresie	
	Finisaj pereti		zugraveli lavabile	zugraveli lavabile	faianta + lavabila	faianta + lavabila	zugraveli lavabile	zugraveli lavabile	zugraveli lavabile	zugraveli lavabile	zugraveli lavabile	
	Finisaj tavane		zugraveli lavabile	zugraveli lavabile	zugraveli lavabile	zugraveli lavabile	zugraveli lavabile	zugraveli lavabile	zugraveli lavabile	zugraveli lavabile	zugraveli lavabile	
	Situatie propusa											
1	Desfacere placaje faianta	mp			14.70	15.75						30.45
2	Desfacere pardoseli din gresie	mp			7.59	4.07	2.57	0.82	4.35	1.36		20.76
3	Desfacere plinte din gresie	ml			-	-	2.80	2.70	5.50	3.60		14.60
4	Desfacere parchet	mp	18.69	11.62		-	-		-			30.31
5	Desfacere plinta din pvc parchet	ml	16.82	12.84								29.66
6	Desfacere sapa de ciment	mp	18.69	11.62	7.59	4.07	2.57	0.82	4.35	1.36	3.14	54.22
7	Sapa de ciment de 3-5 cm grosime	mp	18.69	11.62	7.59	4.07	2.57	0.82	4.35	1.36	3.14	54.22
8	Amorsa suprafete izolatii	mp				4.07					3.14	7.21
9	Hidroizolatii la rece	mp				4.07					3.14	7.21
10	Gresie	mp			7.59	4.07	2.57	0.82	4.35	1.36	3.14	23.90
11	Plinta gresie	ml					2.80	2.70	5.50	3.60	8.16	22.76
12	Amorsare suprafete inainte de autonivelanta	mp	18.69	11.62								30.31
13	Strat suport - sapa autonivelanta	mp	18.69	11.62								30.31
14	Montat parchet laminat	mp	18.69	11.62								30.31
15	plinta parchet	ml	16.82	12.84								29.66
16	Faianta (bucat h=1 m front de lucru + 0,8m +1 m+ baie h=2,10)	mp	-	-	5.33	15.75	-	-	-	-	-	21.08
17	Masti din rigips rez.la umiditate - mascare conducte	mp			2.04							2.04
18	Desfacere tencuieli	mp			14.70	15.75						30.45
19	Tencuieli la pereti	mp			14.70	15.75						30.45

CENTRALIZATOR CANTITATI AP. COLIBRI - STR. JEAN STERIADI

Nr. crt.	Denumire categorii lucrari	U.M.	Camera de zi	Camera	Bucatarie	Baie	Vestibul	Camara	Hol	Debara	Balcon	TOTAL
			1	2	3	4	5	6	7	8	9	9
20	Reparatii tencuieli in jurul tocurilor (ferestre)	ml	6.10	6.64	5.94						8.86	27.54
21	Glet grosier	mp	17.87	12.61	9.19	2.33	3.97	2.31	7.05	3.39	5.07	63.79
22	Glet de finisaj	mp	59.56	42.02	30.65	7.76	13.22	7.71	23.49	11.31	16.91	212.62
23	Spalarea manuala a peretilor	mp	59.56	42.02	30.65	7.76	13.22	7.71	23.49	11.31	16.91	212.62
24	Amorsare suprafete de zugravit	mp	59.56	42.02	30.65	7.76	13.22	7.71	23.49	11.31	16.91	212.62
25	Protejare muchii cu profile metalice-coltare	ml			5.10	5.10						10.20
26	Zugraveli pereti si tavane	mp	59.56	42.02	30.65	7.76	13.22	7.71	23.49	11.31	16.91	212.62
27	Schela petru lucrari de finisaje	mp	18.69	11.62	7.59	4.07	2.57	0.82	4.35	1.36	3.14	54.22
28	Protejare cu folie	mp	18.69	11.62	7.59	4.07	2.57	0.82	4.35	1.36	3.14	54.22
29	Demontare usi din lemn	mp	1.68	1.68	1.68	1.68				1.47		8.19
30	Montare usi din lemn	mp	1.68	1.68	1.68	1.68				1.47		8.19
31	Reparatii tencuieli in jurul tocurilor (usi)	ml	5.00	5.00	5.00	5.00				4.90		24.90
32	Montat profile trecere pardoseala	buc	1.00	1.00								2.00
33	Demontare corp iluminat	buc	1.00	1.00	1.00	1.00	1.00		1.00	1.00		7.00
34	Montare corp de iluminat plafoniera - led	buc	1.00	1.00	1.00	1.00	1.00		1.00	1.00		7.00
35	Demontare intrerupator	buc	1.00	1.00	1.00	1.00	1.00		1.00	1.00		7.00
36	Montare intrerupator	buc	1.00	1.00	1.00	1.00	1.00		1.00	1.00		7.00
37	Demontare priza	buc	2.00	1.00	2.00							5.00
38	Montare priza dubla	buc	2.00	2.00	3.00							7.00
39	Sant in tencuieli -traseu nou prize si iluminat	ml		6.00	6.00							12.00
40	Montat tub protectie dn 16 mm	ml		6.00	6.00							12.00
41	Montare conductor Fy 2,5 mm	ml		18.00	18.00							36.00
42	Astupare sant in tencuieli -trasee noi	ml		6.00	6.00							12.00
43	Canal cablu mascare cu sectiunea 20*40 mm	ml					10.00		10.00			20.00
44	Demontat ventilator	buc				1.00						1.00
45	Montat ventilator	buc				1.00						1.00
46	Demontare oglinda	buc				1.00						1.00
47	Demontare vas WC	buc				1.00						1.00

CENTRALIZATOR CANTITATI AP. COLIBRI - STR. JEAN STERIADI

Nr. crt.	Denumire categorii lucrari	U.M.	Camera de zi	Camera	Bucatarie	Baie	Vestibul	Camara	Hol	Debara	Balcon	TOTAL
			1	2	3	4	5	6	7	8	9	9
48	Demontare cada	buc				1.00						1.00
49	Demontare lavoar	buc				1.00						1.00
50	Demontare baterie lavoar	buc				1.00						1.00
51	Demontare baterie cada cu dus	buc				1.00						1.00
52	Demontare spalator vase	buc			1.00							1.00
53	Demontat baterie spalator	buc			1.00							1.00
54	Demontare robineti	buc			2.00	2.00						4.00
55	Montat oglinda	buc				1.00						1.00
56	Montat WC complet echipat	buc				1.00						1.00
57	Montat lavoar cu mobilier inclus	buc				1.00						1.00
58	Montat baterie lavoar	buc				1.00						1.00
59	Montare cada inclusiv masca	buc				1.00						1.00
60	Montare baterie cada cu dus	buc				1.00						1.00
61	Montat spalator vase	buc			1.00							1.00
62	Montat baterie spalator	buc			1.00							1.00
63	Montat robineti	buc			2.00	2.00						4.00
64	Montat suport hartie igienica	buc				1.00						1.00
65	Montat etajera	buc				1.00						1.00
66	Demontare radiatoare pentru reparatii	mp	2.00	2.00	1.00	1.00						6.00
67	Demontare console	buc				2.00						2.00
68	Montare radiator portprosop	buc				1.00						1.00
69	Montare radiatoare fara procurare (dupa reparatii)	buc	1.00	1.00	1.00							3.00
70	Montare robineti tur	buc	1.00	1.00	1.00	1.00						4.00
71	Montare robineti retur	buc	1.00	1.00	1.00	1.00						4.00
72	Vopsire tevi instalatii	ml	2.50	2.00	4.00	4.00						12.50
73	Incarcare cu lopata moloz si desuri in saci de rafie	to										3.55
74	Transportprin purtare directa moloz si deseuri	to										3.55
75	Incarcare manuala in auto	to										3.55

CENTRALIZATOR CANTITATI AP. COLIBRI - STR. JEAN STERIADI

Nr. crt.	Denumire categorie lucrari	U.M.	Camera de zi	Camera	Bucatarie	Baie	Vestibul	Camara	Hol	Debara	Balcon	TOTAL
			1	2	3	4	5	6	7	8	9	9
76	Incarcare manuala materiale in auto	to										5.80
77	Transport materiale cu auto	to										5.80
78	Descarcare din auto	to										5.80
79	Transport materiale prin purtare directa	to										5.80

Intocmit,