

CENTRALIZATOR CANTITATI CASA NOASTRA

Nr. crt.	Denumire categorie lucrari	U.M.	Hol acces bucatarie	Magazie legume	Bucatarie	Magazie alimente	Grup sanitar personal parter	Grup sanitar parter (cu acces din hol)	Grup sanitar parter (cu acces din hol)	Grup sanitar parter (cu acces din camera - izolator)	TOTAL CANTITATI
			PARTER								
			P1	P2	P3	P4	P6	P15	P16	P20	
	Suprafete (mp)		5.34	4.25	14.60	9.05	2.84	3.12	3.12	2.04	44.35
	Situatie existenta										
	Finisaj pardoseala		gresie	gresie	gresie	gresie	gresie	gresie	gresie	gresie	
	Finisaj pereti		vopsea lavabila	tencuiala calcio	faianta h=2 m + vopsea lavabila	faianta h=2 m+ vopsea lavabila	vopsea lavabila	faianta h =2,10+ vopsea lavabila	faianta h =2,10+ vopsea lavabila	faianta h =1,85+ vopsea lavabila	
	Finisaj tavane		tavan casetat	vopsea lavabila	tavan casetat	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	vopsea lavabila	
	Situatie propusa										
1	Desfacere placaje faianta	mp	-	-	29.56	28.52	14.49	14.49	14.49	6.253	107.81
2	Desfacere pardoseli din gresie	mp	5.34	4.25	14.60	9.05	2.84	3.12	3.12	2.64	44.95
3	Desfacere plinte din gresie	ml	8.80	7.65	-	14.30	-	-	-	-	30.75
4	Desfacere sapa de ciment	mp	5.34	4.25	14.60	9.05	2.84	3.12	3.12	2.64	44.95
5	Sapa de ciment de 3 cm grosime	mp	5.34	4.25	14.60	9.05	2.84	3.12	3.12	2.64	44.95
6	Amorsare suprafete hidroiz	mp	5.34	4.25	14.60	9.05	2.84	3.12	3.12	2.64	44.95
7	Hidroizolatii la rece	mp	5.34	4.25	14.60	9.05	2.84	3.12	3.12	2.64	44.95
8	Gresie	mp	5.34	4.25	14.60	9.05	2.84	3.12	3.12	2.64	44.95
9	Plinta gresie	ml	8.80	7.65	-	14.30	-	-	-	-	30.75
10	Faianta h=2,10	mp	-	-	32.17		14.49	14.49	14.49	7.098	82.74
11	Masti din rigips rez.la umiditate - mascare conducte	mp		2.13	5.72	6.78		2.08	2.08		18.79
12	Desfacere tencuieli	mp	24.43	19.43	29.56	28.52	14.49	14.49	14.49	7.10	152.51
13	Refacere tencuieli	mp	24.43	19.43	29.56	28.52	14.49	14.49	14.49	7.10	152.51
14	Reparatii tencuieli in jurul tocurilor (usi si ferestre)	ml	3.80	0.44	19.60	5.00					28.84
15	Glet grosier	mp	24.43	19.43	9.66	53.60	9.68	9.96	9.96	5.71	142.42
16	Glet de finisaj	mp	24.43	19.43	9.66	53.60	9.68	9.96	9.96	5.71	142.42
17	Spalarea manuala a peretilor	mp	24.43	19.43	9.66	53.60	9.68	9.96	9.96	5.71	142.42
18	Amorsare suprafete de zugravit	mp	24.43	19.43	9.66	53.60	9.68	9.96	9.96	5.71	142.42
19	Protejare muchii cu profile metalice	ml				9.25	4.90	5.20	5.20	7.26	31.81
20	Zugraveli pereti	mp	24.43	19.43	9.66	53.60	9.68	9.96	9.96	5.712	142.42
21	Desfacere tavane casetate	mp	5.34	4.25	14.60						24.19
22	Inlocuire tavane casetate	mp	5.34	4.25	14.60						24.19
23	Schela pemtru lucrari de finisaje	mp	5.34	4.25	14.60	9.05	2.84	3.12	3.12	2.04	44.35
24	Protejare cu folie	mp	5.34	4.25	14.60	9.05	2.84	3.12	3.12	2.04	44.35
25	Carotare pereti AC/hote	buc			1.00						1.00
26	Demontare usi	mp		1.68	1.68	2.36	1.47	1.47	1.47	1.47	11.60
27	montare usi din PVC	mp		1.68	1.68	2.36	1.47	1.47	1.47	1.47	11.60

CENTRALIZATOR CANTITATI CASA NOASTRA

Nr. crt.	Denumire categorie lucrari	U.M.	Hol acces bucatarie	Magazie legume	Bucatarie	Magazie alimente	Grup sanitar personal parter	Grup sanitar parter (cu acces din hol)	Grup sanitar parter (cu acces din hol)	Grup sanitar parter (cu acces din camera - izolator)	TOTAL CANTITATI
PARTER											
			P1	P2	P3	P4	P6	P15	P16	P20	
28	Montat profile trecere pardoseala	buc					1.00	1.00	1.00	1.00	4.00
29	Demontare corp iluminat	buc	2.00	1.00	2.00	1.00	1.00	1.00	1.00	1.00	10.00
30	Montare corp de iluminat - led	buc					1.00	1.00	1.00	1.00	4.00
31	Montare corp iluminat tip panou led 600x600 ingropat	buc	2.00	1.00	2.00	1.00					6.00
32	Demontare intrerupator	buc	1.00	1.00	2.00	1.00	1.00	1.00	1.00	1.00	9.00
33	Montare intrerupator	buc	1.00	1.00	2.00	1.00	1.00	1.00	1.00	1.00	9.00
34	Demontare priza	buc			3.00	4.00		1.00	1.00		9.00
35	Montare priza dubla	buc			6.00	6.00		1.00	1.00		14.00
36	Sant in tencuieli -traseu nou prize si iluminat	ml			18.00	12.00		6.00	6.00		42.00
37	Montat tub protectie dn 16 mm	ml			18.00	12.00		6.00	6.00		42.00
38	Montare conductor Fy 2,5 mm	ml			54.00	36.00		18.00	18.00		126.00
39	Montare conductor Fy 1,5 mm	ml			18.00	18.00					36.00
40	Astupare sant in tencuieli	ml			18.00	12.00		6.00	6.00		42.00
41	Canal cablu mascare cu sectiunea 20*40 mm	ml			10.00						10.00
42	Demontat ventilator	buc					1.00	1.00	1.00		3.00
43	Montat ventilator	buc			1.00		1.00	1.00	1.00		4.00
44	Demontare oglinda	buc					1.00	1.00	1.00	1.00	4.00
45	Demontare vas WC	buc					1.00	1.00	1.00	1.00	4.00
46	Demontare cada dus	buc								1.00	1.00
47	Demontare lavoar	buc					1.00	1.00	1.00	1.00	4.00
48	Demontare baterie lavoar	buc					1.00	1.00	1.00	1.00	4.00
49	Demontare baterie cada cu dus	buc								1.00	1.00
50	Demontare spalator vase	buc			2.00						2.00
51	Demontat baterie spalator	buc			2.00						2.00
52	Demontare robineti	buc			6.00		2.00	2.00	2.00	2.00	14.00
53	demontare tevi PPR	ml									30.00
54	Montare tevi PPR	ml									30.00
55	Demontare tevi scurgere PP	ml									20.00
56	Montat scurgeri PP	ml									20.00
57	Montat spalator profesional (fara procurare spalator)	buc			2.00						2.00
58	Montat baterie spalator profesional (fara procurarespalator)				2.00						2.00
59	Montat oglinda	buc					1.00	1.00	1.00	1.00	4.00
60	Montat vas WC	buc					1.00	1.00	1.00	1.00	4.00
61	Montat lavoar cu mobilier	buc					1.00	1.00	1.00	1.00	4.00

CENTRALIZATOR CANTITATI CASA NOASTRA

Nr. crt.	Denumire categorie lucrari	U.M.	Hol acces bucatarie	Magazie legume	Bucatarie	Magazie alimente	Grup sanitar personal parter	Grup sanitar parter (cu acces din hol)	Grup sanitar parter (cu acces din hol)	Grup sanitar parter (cu acces din camera - izolator)	TOTAL CANTITATI
PARTER											
			P1	P2	P3	P4	P6	P15	P16	P20	
62	Montat baterie lavoar	buc					1.00	1.00	1.00	1.00	4.00
63	Zidarie bca (perimetral creare cadita dus	ml								1.40	1.40
64	Montare cadita dus extraplata	buc									0.00
65	Montare baterie cada cu dus	buc								1.00	1.00
66	Montat robineti	buc			6.00		2.00	2.00	2.00	2.00	14.00
67	Montare rigola scurgere dus	buc								1.00	1.00
68	Montat suport hartie igienica	buc					1.00	1.00	1.00	1.00	4.00
69	Montat etajera	buc					1.00	1.00	1.00	1.00	4.00
70	Demontare radiatoare	buc	1.00		1.00		1.00	1.00	1.00	1.00	6.00
71	Demontare console	buc			2.00						2.00
72	Demontare teava pexal 1/2"	ml			10.00	30.00					40.00
73	Demontare teava neagra inst de incalzire 1/2"	ml	10.00				6.00	10.00	10.00	6.00	42.00
74	Montare teava PPR gri cu fibra compozita 20 mm	ml			10.00	30.00	6.00	10.00	10.00	6.00	72.00
75	Montat fittinguri PP-R teu egal PP R gri 20 mm	buc			2.00	12.00	2.00	4.00	4.00	2.00	26.00
76	Montare radiator portprosop	buc					1.00	1.00	1.00	1.00	4.00
77	Radiator otel 1000x600	buc	1.00		1.00						2.00
78	Montare robineti tur retur	buc	2.00		2.00		2.00	2.00	2.00	2.00	12.00
79	Incarcare cu lopata moloz si desuri in saci de rafie	to									10.22
80	Transport prin purtare directa moloz si deseuri	to									10.22
81	Incarcare manuala in auto	to									10.22
82	Incarcare manuala materiale in auto	to									15.10
83	Transport materiale cu auto	to									15.10
84	Descarcare din auto	to									15.10
85	Transport materiale prin purtare directa	to									15.10