

CENTRALIZATOR SITUATIE EXISTENTA - LUCRARI PROPUSE - INSTALATII ELECTRICE

Nr. crt.	Denumire categorii lucrari	U.M.	TOTAL	Parter																											
				Dormitor	Sala activitati		Debara	Debara	Debara	Izolator	Grup sanitar izolator	Hol izolator	Hol intrare spate	Hol	Birou	Grup sanitar director	Hol grup sanitar	Birou director	Sala activitati	Dormitor	Dormitor	Sala mese	Hol	Debara	Debara	Debara	Grup sanitar baieti	Dusuri baieti	Grup sanitar baieti	Cabina WC baieti	Cabina WC baieti
					01	02																									
SITUATIE EXISTENTA																															
1	Tablou electric		5																												
2	FIPAD 1x18W		6										1														2				
3	FIPAD 2x18W		9							1																		4			
4	FIPAD 2x36W		27										1	1							1	2									
5	FIDA 2x18W		2																2												
6	FIDA 1x36W		1										1																		
7	FIRA 4x18W		1			1																									
8	Aplica tavan 1x60W		2														1														
9	Aplica perete 1x18W		2																		2										
10	Aplica perete 1x60W		5			1									1							2									
11	FIRA 2x36W		10	2	1													2			1										
12	Dulie E27 (fasung) + bec		2								1																				
13	BADT 1x60W		2																												
14	Corp iluminat EXIT		7	1									1						1	1						1					
15	Intrerupator ST		10									1			1																
16	Intrerupator PT		6			1												1		1											
17	Comutator ST		19		1						1			1			1	2				2				2					
18	Comutator PT		2		1																										
19	Priza simpla PT		32	1	2	1								1				2			1	3	2								
20	Priza dubla ST		4																												
21	Priza dubla PT		11											2			3	1													
SITUATIE PROPUSA																															
1	Demontare corpuri de iluminat	buc	76	3	1	2					1	1	1	3	1	1		1	2	3	3	4	2				3	4			
2	Demontare aparate electrice	buc	84	1	4	2						1			4	1		4	6		2	3	4				2				
3	Montare corp de iluminat cu tuburi LED tip FIPAD 1x18W	buc	8											1													2				
4	Montare corp de iluminat cu tuburi LED tip FIPAD 2x18W	buc	6								1																	4			
5	Montare corp de iluminat cu tuburi LED tip FIPAD 2x36W	buc	11																												
6	Montare corp de iluminat tip panou LED 300x600 aparent	buc	6											1					2												
7	Montare corp de iluminat tip panou LED 600x600 aparent	buc	30	2	1	1								1	1			1	2		2	2									
8	Montare corp de iluminat tip EXIT	buc	7	1										1						1	1						1				
9	Montare corp de iluminat cu LED tip aplica perete	buc	8			1						1				1					2	2									
10	Montare tuburi LED 9w, 60 cm	buc	20								2			1													2	8			
11	Montare tuburi LED 18w, 120 cm	buc	22																												
12	Montare Intrerupator ST	buc	16											1			1										3				
13	Montare Intrerupator PT	buc	6			1													1		1										
14	Montare Comutator ST	buc	19		1							1			1			1	2				2				2				
15	Montare Comutator PT	buc	2		1																										
16	Montare Priza simpla PT	buc	32	1	2	1									1				2			1	3	2							
17	Montare Priza dubla ST	buc	4																												
18	Montare Priza dubla PT	buc	11												2			3	1												
19	Sapare santuri in pereti	m	60																									30			
20	Montare tub protectie ø16 mm	m	60																									30			
21	Montare cablu Cyy-F 2x1,5 mmp	m	60																									30			
22	Astupare santuri in pereti	buc	60																									30			
23	Verificari si incercari electrice la corpuri iluminat	buc	76	3	1	2					1	1	1	3	1	1		1	2	3	3	4	2				3	4			
24	Verificari si incercari electrice la circuite iluminat si prize	buc	90	1	4	2						1	1		4	1		4	6		2	3	4				5				

CENTRALIZATOR SITUATIE EXISTENTA - LUCRARI PROPUSE - INSTALATII ELECTRICE

Nr. crt.	Denumire categorii lucrari	U.M.	TOTAL	Parter																										
				Cabina WC baieti	Debara	Debara	Debara	Salon	Hol	Bucatarie	Bucatarie	Camara	Hol intrare principala	Magazie alimente	Cabina WC	Grup sanitar	Cabina dus	Hol	Grup sanitar fete	Cabina WC fete	Cabina WC fete	Cabina WC fete	Grup sanitar fete	Dusuri fete	Debara	Debara	Debara	Birou	Sala activitati	Dormitor
				29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55

SITUATIE EXISTENTA

1	Tablou electric		5					1						1				1												
2	FIPAD 1x18W		6													1														
3	FIPAD 2x18W		9										1					2												
4	FIPAD 2x36W		27					8		2	1			1				3	1				1							
5	FIDA 2x18W		2																											
6	FIDA 1x36W		1																											
7	FIRA 4x18W		1																											
8	Aplica tavan 1x60W		2																											
9	Aplica perete 1x18W		2																											
10	Aplica perete 1x60W		5																										1	
11	FIRA 2x36W		10																										2	2
12	Dulie E27 (fasung) + bec		2									1																		
13	BADT 1x60W		2												1		1													
14	Corp iluminat EXIT		7															1												1
15	Intrerupator ST		10							1		1						1											1	
16	Intrerupator PT		6								1																			
17	Comutator ST		19					1					1	1		2		1											2	
18	Comutator PT		2																										1	
19	Priza simpla PT		32					4			2							2											3	
20	Priza dubla ST		4											3																
21	Priza dubla PT		11									1						1											1	

SITUATIE PROPUASA

1	Demontare corpuri de iluminat	buc	76					8		2	1	1	1	1	1	1	1	6	1					1						3	3
2	Demontare aparate electrice	buc	84					5		1	3	2	1	4		2		5												8	
3	Montare corp de iluminat cu tuburi LED tip FIPAD 1x18W	buc	8									1			1	1	1														
4	Montare corp de iluminat cu tuburi LED tip FIPAD 2x18W	buc	6																												
5	Montare corp de iluminat cu tuburi LED tip FIPAD 2x36W	buc	11							2	1			1					1					1							
6	Montare corp de iluminat tip panou LED 300x600 aparent	buc	6										1					2													
7	Montare corp de iluminat tip panou LED 600x600 aparent	buc	30					8										3											2	2	
8	Montare corp de iluminat tip EXIT	buc	7															1												1	
9	Montare corp de iluminat cu LED tip aplica perete	buc	8																										1		
10	Montare tuburi LED 9w, 60 cm	buc	20									1			1	1	1														
11	Montare tuburi LED 18w, 120 cm	buc	22							4	2			2					2					2							
12	Montare Intrerupator ST	buc	16							1		1						1						3					1		
13	Montare Intrerupator PT	buc	6								1																				
14	Montare Comutator ST	buc	19					1					1	1		2		1											2		
15	Montare Comutator PT	buc	2																										1		
16	Montare Priza simpla PT	buc	32					4			2							2											3		
17	Montare Priza dubla ST	buc	4											3																	
18	Montare Priza dubla PT	buc	11									1						1											1		
19	Sapare santuri in pereti	m	60																					30							
20	Montare tub protectie ø16 mm	m	60																					30							
21	Montare cablu Cyy-F 2x1,5 mmp	m	60																					30							
22	Astupare santuri in pereti	buc	60																					30							
23	Verificari si incercari electrice la corpuri iluminat	buc	76					8		2	1	1	1	1	1	1	1	6	1					1					3	3	
24	Verificari si incercari electrice la circuite iluminat si prize	buc	90					5		1	3	2	1	4		2		5						3					8		

CENTRALIZATOR SITUATIE EXISTENTA - LUCRARI PROPUSE - INSTALATII ELECTRICE

Nr. crt.	Denumire categorii lucrari	U.M.	TOTAL	Parter								
				Casa scarii subsol	Magazie subsol	Uscatorii	Spatorii	Calcatorii	Administrator	Administrator	Curte spate	TOTAL
				56	57	58	59	60	61	62		

SITUATIE EXISTENTA

1	Tablou electric		5			1	1					5
2	FIPAD 1x18W		6			1			1			6
3	FIPAD 2x18W		9				1					9
4	FIPAD 2x36W		27	1	1		1	1			1	27
5	FIDA 2x18W		2									2
6	FIDA 1x36W		1									1
7	FIRA 4x18W		1									1
8	Aplica tavan 1x60W		2							1		2
9	Aplica perete 1x18W		2									2
10	Aplica perete 1x60W		5									5
11	FIRA 2x36W		10									10
12	Dulie E27 (fasung) + bec		2									2
13	BADT 1x60W		2									2
14	Corp iluminat EXIT		7									7
15	Intrerupator ST		10	1				1	1	1		10
16	Intrerupator PT		6			1					1	6
17	Comutator ST		19				1					19
18	Comutator PT		2									2
19	Priza simpla PT		32				6	2				32
20	Priza dubla ST		4							1		4
21	Priza dubla PT		11							1	1	11

SITUATIE PROPUSA

1	Demontare corpuri de iluminat	buc	76	1	1	1	2	1	1	1	1	76
2	Demontare aparate electrice	buc	84	1		1	7	3	1	3	2	84
3	Montare corp de iluminat cu tuburi LED tip FIPAD 1x18W	buc	8			1						8
4	Montare corp de iluminat cu tuburi LED tip FIPAD 2x18W	buc	6				1					6
5	Montare corp de iluminat cu tuburi LED tip FIPAD 2x36W	buc	11	1	1		1	1			1	11
6	Montare corp de iluminat tip panou LED 300x600 aparent	buc	6									6
7	Montare corp de iluminat tip panou LED 600x600 aparent	buc	30						1	1		30
8	Montare corp de iluminat tip EXIT	buc	7									7
9	Montare corp de iluminat cu LED tip aplica perete	buc	8									8
10	Montare tuburi LED 9w, 60 cm	buc	20			1	2					20
11	Montare tuburi LED 18w, 120 cm	buc	22	2	2		2	2			2	22
12	Montare Intrerupator ST	buc	16	1				1	1	1		16
13	Montare Intrerupator PT	buc	6			1					1	6
14	Montare Comutator ST	buc	19				1					19
15	Montare Comutator PT	buc	2									2
16	Montare Priza simpla PT	buc	32				6	2				32
17	Montare Priza dubla ST	buc	4							1		4
18	Montare Priza dubla PT	buc	11							1	1	11
19	Sapare santuri in pereti	m	60									60
20	Montare tub protectie ø16 mm	m	60									60
21	Montare cablu Cyy-F 2x1,5 mmp	m	60									60
22	Astupare santuri in pereti	buc	60									60
23	Verificari si incercari electrice la corpuri iluminat	buc	76	1	1	1	2	1	1	1	1	76
24	Verificari si incercari electrice la circuite iluminat si prize	buc	90	1		1	7	3	1	3	2	90