

CENTRALIZATOR SUPRAFETE, CANTITATI

Nr. crt.	Denumire categorie	U.M.	Parter												
			Windfang intrare principala	Casa scarii 1	Sala asteptare	Uscatorie calcatorii	Depozit rufe curate	Spalatorie	Depozit rufe murdare	Sas spalatorie	Grup sanitar spalatorie	Hol Casa scarii 2	Hol intrare bucatarie	Depozit alimente	Hol bucatarie
			01	02	03	19	20	21	22	23	24	40	41	42	43

SUPRAFETE EXISTENTE

1	Suprafete tavane lavabila existente	mp	5,18	15,68	36,76	12,16	9,12	16,72	7,80	1,96	8,06	9,57	3,54	10,74	9,48
2	Suprafete pereti lavabila existente	mp	17,88	37,41	72,53	7,00	6,20	8,94	5,65	2,80	12,78	24,55	4,57	7,54	19,47
3	Suprafete vinarom existente	mp	23,06	53,09	109,29	19,16	15,32	25,66	13,45	4,76	20,84	34,12	8,11	18,28	28,95

LUCRARI PROPUSE

1	Spalare suprafete la pereti si tavane	mp	23,06	53,09	109,29	19,16	15,32	25,66	13,45	4,76	20,84	34,12	8,11	18,28	28,95
2	Glet ipsos grosier	mp	2,31	5,31	10,93	1,92	1,53	2,57	1,35	0,48	2,08	3,41	0,81	1,83	2,89
3	Glet ipsos de finisaj	mp	18,45	42,47	87,43	15,33	12,26	20,53	10,76	3,81	16,67	27,30	6,49	14,62	23,16
4	Zugraveli lavabile la per. si tav.	mp	23,06	53,09	109,29	19,16	15,32	25,66	13,45	4,76	20,84	34,12	8,11	18,28	28,95
5	Protejare cu folie	mp	5,18	15,68	36,76	12,16	9,12	16,72	7,80	1,96	8,06	9,57	3,54	10,74	9,48
6	Montare si demontare schela	mp	5,18	15,68	36,76	12,16	9,12	16,72	7,80	1,96	8,06	9,57	3,54	10,74	9,48

CENTRALIZATOR SUPRAFETE, CANTITATI

Nr. crt.	Denumire categorie	U.M.					Etaj 1			TOTAL GENERAL
			Camera frigidere	Bucatarie	Oficiu bucatarie	TOTAL PARTER	Casa scarii 1	Oficiu alimentar	TOTAL ETAJ 1	
			44	45	46		01	39		

SUPRAFETE EXISTENTE

1	Suprafete tavane lavabila existente	mp	7,98	31,92	15,12	201,79	15,68	19,47	35,15	236,94
2	Suprafete pereti lavabila existente	mp	6,22	12,65	60,74	306,92	37,31	12,05	49,36	356,28
3	Suprafete vinarom existente	mp	14,19	44,57	75,86	508,71	52,99	31,52	84,51	593,22

LUCRARI PROPUSE

1	Spalare suprafete la pereti si tavane	mp	14,19	44,57	75,86	508,71	52,99	31,52	84,51	593,22
2	Glet ipsos grosier	mp	1,42	4,46	7,59	50,87	5,30	3,15	8,45	59,32
3	Glet ipsos de finisaj	mp	11,35	35,66	60,69	406,97	42,39	25,22	67,61	474,57
4	Zugraveli lavabile la per. si tav.	mp	14,19	44,57	75,86	508,71	52,99	31,52	84,51	593,22
5	Protejare cu folie	mp	7,98	31,92	15,12	201,79	15,68	19,47	35,15	236,94
6	Montare si demontare schela	mp	7,98	31,92	15,12	201,79	15,68	19,47	35,15	236,94