

CENTRALIZATOR SITUATIE EXISTENTA - LUCRARI PROPUSE - INSTALATII INCALZIRE

Nr. crt.	Denumire categorii lucrari	U.M.	Putere totala	TOTAL	Parter							
					Grup sanitar izolato	Grup sanitar director	Sala mese	Salon	Cabina WC	Grup sanitar	Administrator	TOTAL
					08	13	19	33	40	41	62	

INSTALATII INCALZIRE

SITUATIE EXISTENTA

1	Radiator fonta 6 elem. 2CU-600/2-60 (L=0,360 m, P=750 w)	buc	2.250	3	1	1			1			3
2	Radiator fonta 9 elem. 2CU-600/2-60 (L=0,540 m, P=1.125 w)	buc	1.125	1						1		1
8	Radiator fonta 30 elem. 2CU-600/2-60 (L=1,800 m, P=3.750 w)	buc	7.500	2				2				2
13	Radiator fonta 33 elem. 3CU 600/3-60 (L=1,650 m, P=5.016 w)	buc	5.016	1			1					1
14	Radiator fonta 20 elem. 9CL 218/9 (L=1,000 m, P=2.480 w) (desfiintare)	buc	2.480	1			1					1
17	Radiator otel 22x600x800 (P=1.821 w)	buc	3.642	2				1			1	2
18	Radiator otel 22x600x900 (P=2.048 w)	buc	2.048	1				1				1
23	Robinet radiator coltar tur 1/2"	buc		11	1	1	2	4	1	1	1	11
24	Robinet radiator coltar retur 1/2"	buc		11	1	1	2	4	1	1	1	11
25	Suprafata incalzire radiatoare fonta 2CU-600/2-60	mp		23,06	1,59	1,59		15,90	1,59	2,39		23,06
26	Suprafata incalzire radiatoare fonta 3CU 600/3-60	mp		11,06			11,06					11,06
27	Suprafata incalzire radiatoare fonta 9CL 218/9	mp		5,52			5,52					5,52
28	Suprafata incalzire radiatoare otel	mp		12,43				8,45			3,98	12,43
30	Suprafata incalzire radiatoare TOTAL	mp		52,06	1,59	1,59	16,58	24,35	1,59	2,39	3,98	52,06
31	Greutate totala radiatoare	kg		1.148	41	41	467	469	41	62	26	1.148

SITUATIE PROPUSA

1	Demontare radiatoare din fonta, otel sau aluminiu	mp		52,06	1,59	1,59	16,58	24,35	1,59	2,39	3,98	52,06
2	Demontare robinete	buc		22	2	2	4	8	2	2	2	22
4	Montare radiator tip panou din otel tip 22/600x500 (P=1.138 w)	buc	1.138	1						1		1
7	Montare radiator tip panou din otel tip 22/600x800 (P=1.821 w)	buc	3.642	2				1			1	2
8	Montare radiator tip panou din otel tip 22/600x900 (P=2.048 w)	buc	2.048	1				1				1
12	Montare radiator tip panou din otel tip 22/600x1800 (P=4.097 w)	buc	8.194	2				2				2
15	Montare radiator tip panou din otel tip 33/600x1600 (P=5.130 w)	buc	5.130	1			1					1
16	Montare radiator tip portprosop din otel tip Padova 400x650 (P=266 w)	buc	798	3	1	1			1			3
18	Montare robinete coltar tur 1/2"	buc		10	1	1	1	4	1	1	1	10
19	Montare robinete coltar retur 1/2"	buc		10	1	1	1	4	1	1	1	10
20	Demontare teava neagra 1/2"	m		24	8	8			8			24
21	Montare teava pp-r cu fibra compozita, d=20 mm	m		24	8	8			8			24
22	Montare colier cu garnitura, d=20-23 mm	buc		12	4	4			4			12
23	Montare racord pp-r, FE, d=1/2"-20 mm	buc		6	2	2			2			6
24	Proba de etanseitate la presiune a instalatiei de incalzire	mp		44,75	0,26	0,26	11,16	26,35	0,26	2,49	3,98	44,75
25	Probe preliminare de dilatare-contractie a instalatiei de incalzire	mp		44,75	0,26	0,26	11,16	26,35	0,26	2,49	3,98	44,75
26	Evacuare deseuri	to		1,15	0,04	0,04	0,47	0,47	0,04	0,06	0,03	1,15