

Formular F3

Obiectiv: 009 DGASPC SECTOR 3

LISTA

cu cantitatile de lucrari pe categorii de lucrari

Obiect: 01 IGIENIZARI

Categorie: 01 CENTRUL LIZUCA

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	
1	RPCJ18C 99	MP	944.04000		
GLET DIN IPSOS GROSIER LA PERETI SI TAVANE, 3 MM GROSIME					
2	RPCJ18D 99	MP	3,146.82000		
GLET DIN IPSOS DE FINISAJ LA PERETI SI TAVANE, 1 MM GROSIME					
3	RPCJ34A 99	MP	3,146.82000		
SPALAREA MANUALA A SUPRAFETELOR LA PERETI SI TAVANE					
4	RPCE01B 99	MP	3,146.82000		
AMORSARE SUPRAFETE PENTRU EXECUTARE ZUGRAVELI LAVABILE					
5	RPCR24A 99	MP	3,146.82000		
ZUGRAVELI INTERIOARE LAVABILE, LA PERETI SI TAVANE					

6	RPCH31D 99	MP	1,132.84000		
L: LC68K -M :9C00326 -VOPSEA LAVABILA PENTRU INTERIOR - CULOARE ALBA					
MONTARE SI DEMONTARE SCHELA METALICA PENTRU LUCRARI DE FINISAJE					
7	H1B16G 82	MP	1,132.84000		
PROTEJARE SUPRAFETE PRIN ACOPERIRE CU FOLIE DE POLIETILENA					

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	

8	RPEF23B 99	BUCATA		54.00000	
---	------------	--------	--	----------	--

DEMONTARE CORPURI DE ILUMINAT

9	RPEF02A 99	BUCATA		40.00000	
---	------------	--------	--	----------	--

MONTARE CORP DE ILUMINAT TIP FIPAD, ECHIPAT CU TUBURI LED 2X9 W

L: EL21B -M :9004014 -CORP DE ILUMINAT FLUORESCENT ETANS FIPAD 05 - 2 X 9 W

10	RPEF12B 99	BUCATA		80.00000	
----	------------	--------	--	----------	--

MONTARE TUBURI LED 9W, 60 CM

L: EL21Y -M :9E00639 -TUB LED, T8, 9 W, 60 CM, 6400K

11	RPEF19A 99	BUCATA		14.00000	
----	------------	--------	--	----------	--

MONTARE CORP DE ILUMINAT DE EXTERIOR, TIP PROIECTOR CU LED, 230V/150W, 6500K, IP65, 13.500LM

L: EL21Z2 -M :9E00670 -PROIECTOR LED 230V/150W, 6500K, IP65, 13.500LM

12	TRB04B1 99	TONE		1.58000	
----	------------	------	--	---------	--

INCARCARE CU LOPATA MOLOZ SI DESEURI IN SACI DE RAFIE SAU IUTA

13	TRB05B1I 99	TONE		1.58000	
----	-------------	------	--	---------	--

TRANSPORT PRIN PURTARE DIRECTA MOLOZ SI DESEURI

C:01:1.00:PENTRU MATERIALE INCOMODE

14	TRI1AA01F 99	TONE		1.58000	
----	--------------	------	--	---------	--

INCARCARE MANUALA MOLOZ SI DESEURI IN AUTO

15	TRA01A30P 82	TONE		1.58000	
----	--------------	------	--	---------	--

TRANSPORT RUTIER MOLOZ CU AUTOBASCULANTA LA 30 KM

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a)materiale	
	Denumire resursa			b)manopera	
	Observatii			c)utilaj	
	Corectii			d)transport	
	Liste Anexe			Total(a+b+c+d)	
16	TRI1AA01F 99	TONE			13.40000

INCARCARE MANUALA MATERIALE IN AUTO

17	TRA02A20 82	TONE			13.40000
----	-------------	------	--	--	----------

TRANSPORT RUTIER MATERIALE CU AUTOCAMIONUL LA 20 KM

18	TRI1AA08F 99	TONE			13.40000
----	--------------	------	--	--	----------

DESCARCARE MANUALA MATERIALE DIN AUTO

19	TRB05B1I 99	TONE			13.40000
----	-------------	------	--	--	----------

TRANSPORT PRIN PURTARE DIRECTA MATERIALE

C:01:1.00:PENTRU MATERIALE INCOMODE

OFERTANT,