

Formular F3

Obiectiv: 009 DGASPC SECTOR 3

LISTA

cu cantitatile de lucrari pe categorii de lucrari

Obiect: 01 IGIENIZARI

Categorie: 02 CENTRUL SF. MARIA

| Nr. | Capitol lucrari | U/M | Cantitatea | Pretul unitar | Valoare |
|--|------------------|-----|-------------|----------------|---------|
| Crt. | Simbol | | | a)materiale | |
| | Denumire resursa | | | b)manopera | |
| | Observatii | | | c)utilaj | |
| | Corectii | | | d)transport | |
| | Liste Anexe | | | Total(a+b+c+d) | |
| 1 | RPCJ18C 99 | MP | 304.72000 | | |
| GLET DIN IPSOS GROSIER LA PERETI SI TAVANE, 3 MM GROSIME | | | | | |
| 2 | RPCJ18D 99 | MP | 1,015.74000 | | |
| GLET DIN IPSOS DE FINISAJ LA PERETI SI TAVANE, 1 MM GROSIME | | | | | |
| 3 | RPCJ34A 99 | MP | 1,015.74000 | | |
| SPALAREA MANUALA A SUPRAFETELOR LA PERETI SI TAVANE | | | | | |
| 4 | RPCE01B 99 | MP | 1,015.74000 | | |
| AMORSARE SUPRAFETE PENTRU EXECUTARE ZUGRAVELI LAVABILE | | | | | |
| 5 | RPCR24A 99 | MP | 1,015.74000 | | |
| ZUGRAVELI INTERIOARE LAVABILE, LA PERETI SI TAVANE | | | | | |
| ----- | | | | | |
| 6 | RPCH31D 99 | MP | 276.63000 | | |
| L: LC68K -M :9C00326 -VOPSEA LAVABILA PENTRU INTERIOR - CULOARE ALBA | | | | | |
| MONTARE SI DEMONTARE SCHELA METALICA PENTRU LUCRARI DE FINISAJE | | | | | |
| 7 | H1B16G 82 | MP | 276.63000 | | |
| PROTEJARE SUPRAFETE PRIN ACOPERIRE CU FOLIE DE POLIETILENA | | | | | |
| 8 | RPCQ05J 99 | MP | 0.90000 | | |

| Nr. Crt. | Capitol lucrari Simbol Denumire resursa Observatii Corectii Liste Anexe | U/M | Cantitatea | Pretul unitar a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d) | Valoare |
|--|--|--------|------------|---|---------|
| INLOCUIRE GEAM TERMOIZOLANT | | | | | |
| ----- | | | | | |
| L: LC42 -M :9C00569 -GEAM TERMOIZOLANT FLOAT CLAR | | | | | |
| 9 | RPEE24A 99 | BUCATA | | 12.00000 | |
| DEMONTARE APARATE ELECTRICE UNIPOLARE (INTRERUPATOARE, COMUTATOARE, PRIZE, ETC) | | | | | |
| ----- | | | | | |
| 10 | RPEE03B 99 | BUCATA | | 12.00000 | |
| MONTARE PRIZA DUBLA ST CU CP, 16A / 250V | | | | | |
| ----- | | | | | |
| L: EL03E -0032:7319280 -DOZE PT.APARATE PT.TUBURI IZOLANTE USOR PROTEJATE -AIP | | | | | |
| L: EL18D -M :9E00402 -PRIZA DUBLA ST CU CP 16A/250V | | | | | |
| 11 | RPEA09D 99 | M | | 20.00000 | |
| MONT.ELEM.PROT.DIN MAT.PLASTIC,APARENT PE PERETE SAU IN CANALE,PT.MASCAREA CABL.EL.D=40X20 MM | | | | | |
| ----- | | | | | |
| L: EL01C -M :9E00508 -CANAL CABLU DIN PVC 40 X 20 MM | | | | | |
| L: EL18A -M :9000433 -DIBLU CU HOLTESURUB 6 X 42 | | | | | |
| 12 | TRB04B1 99 | TONE | | 0.43700 | |
| INCARCARE CU LOPATA MOLOZ SI DESEURI IN SACI DE RAFIE SAU IUTA | | | | | |
| ----- | | | | | |
| 13 | TRB05B1I 99 | TONE | | 0.43700 | |
| TRANSPORT PRIN PURTARE DIRECTA MOLOZ SI DESEURI | | | | | |
| ----- | | | | | |
| C: 01:1.00:PENTRU MATERIALE INCOMODE | | | | | |
| 14 | TRI1AA01F 99 | TONE | | 0.43700 | |
| INCARCARE MANUALA MOLOZ SI DESEURI IN AUTO | | | | | |
| ----- | | | | | |
| 15 | TRA01A30P 82 | TONE | | 0.43700 | |
| TRANSPORT RUTIER MOLOZ CU AUTOBASCULANTA LA 30 KM | | | | | |
| ----- | | | | | |
| 16 | TRI1AA01F 99 | TONE | | 4.14800 | |

| Nr. | Capitol lucrari | U/M | Cantitatea | Pretul unitar | Valoare |
|------|------------------|-----|------------|----------------|---------|
| Crt. | Simbol | | | a)materiale | |
| | Denumire resursa | | | b)manopera | |
| | Observatii | | | c)utilaj | |
| | Corectii | | | d)transport | |
| | Liste Anexe | | | Total(a+b+c+d) | |

INCARCARE MANUALA MATERIALE IN AUTO

| | | | | |
|----|----------|----|------|---------|
| 17 | TRA02A20 | 82 | TONE | 4.14800 |
|----|----------|----|------|---------|

TRANSPORT RUTIER MATERIALE CU AUTOCAMIONUL LA 20 KM

| | | | | |
|----|-----------|----|------|---------|
| 18 | TRI1AA08F | 99 | TONE | 4.14800 |
|----|-----------|----|------|---------|

DESCARCARE MANUALA MATERIALE DIN AUTO

| | | | | |
|----|----------|----|------|---------|
| 19 | TRB05B1I | 99 | TONE | 4.14800 |
|----|----------|----|------|---------|

TRANSPORT PRIN PURTARE DIRECTA MATERIALE

C:01:1.00:PENTRU MATERIALE INCOMODE

OFERTANT,